

1711 Florida Avenue NW
Garage Reuse Concept Design

June 3, 2014

PROPERTY DESCRIPTION	
STREET ADDRESS	1711 FLORIDA AVENUE NW
SQUARE AND LOT	SQUARE 2562, LOT 0095
ZONING CLASSIFICATION	C-2-B
OVERLAY DISTRICT	RC (REED COOKE)
HISTORIC DISTRICT	NONE
TYPE OF LOT	COMMERCIAL
LOT SIZE	25920 SF
PROPERTY USE	EXISTING: COMMERCIAL, PARKING GARAGE PROPOSED: APARTMENT HOUSE, 129 DWELLING UNITS

DEVELOPMENT DENSITY			
SECTION	DESCRIPTION	PERMITTED	PROPOSED
771.2	FLOOR AREA RATIO (C-2-B)	3.5 FAR APARTMENT HOUSE	
		1.5 FAR OTHER USE	
		3.5 FAR MAXIMUM	
2604.1	BONUS DENSITY (INCLUSIONARY ZONING)	20% BONUS 0.7 FAR	
		4.2 FAR MAXIMUM W/BONUS	4.06 FAR

USE BY AREA	
	PROPOSED
CELLAR 1	19,205
TOTAL BELOW GRADE	19,205
FIRST FLOOR	22,932
SECOND FLOOR	20,602
THIRD FLOOR	20,602
FOURTH FLOOR	20,602
FIFTH FLOOR	20,602
TOTAL ABOVE GRADE	105,340

BUILDING HEIGHT			
SECTION	DESCRIPTION	PERMITTED	PROPOSED
770.1	BUILDING HEIGHT (C-2-B)	65 FEET	54.83 FEET
1402.1	BUILDING HEIGHT (RC OVERLAY)	40 FEET	
		50 FEET (IZ BONUS)	

LOT OCCUPANCY			
SECTION	DESCRIPTION	PERMITTED	PROPOSED
772.1	LOT OCCUPANCY (C-2-B)	80% FOR RESIDENTIAL USE	79.5% RESIDENTIAL USE
		N/A FOR NON-RESIDENTIAL USE	88.5% TOTAL AT GROUND FLOOR INCLUDES AREA DEVOTED TO PARKING/LOADING USE
2604.2	LOT OCCUPANCY (C-2-B WITH IZ) (INCLUSIONARY ZONING)	80% FOR RESIDENTIAL USE N/A FOR NON-RESIDENTIAL USE	

REAR YARD				
SECTION	DESCRIPTION	REQUIRED	EXISTING	PROPOSED
774.1	REAR YARD (C-2-B)	15 FEET	VARIES (0 FEET MIN)	EXISTING AT GROUND FLOOR 15 FEET AT ALL NEW CONSTRUCTION

SIDE YARD				
SECTION	DESCRIPTION	REQUIRED	EXISTING	PROPOSED
775.5	SIDE YARD (C-2-B)	NONE	NONE	NONE

COURTS			
SECTION	DESCRIPTION	REQUIRED	PROPOSED
776.3	OPEN COURTS (C-2-B)	15 FEET MIN OR 4" PER FT OF BUILDING HEIGHT	38 FEET
776.3	CLOSED COURTS (C-2-B)	15 FEET MIN OR 4" PER FT OF BUILDING HEIGHT	
776.4	CLOSED COURT MINIMUM AREA	350 SF AND 2X SQUARE OF MIN WIDTH	

OFF-STREET PARKING			
SECTION	DESCRIPTION	REQUIRED	PROPOSED
2101.1	OFF-STREET PARKING (C-2-B)	1 PER 3 DWELLING UNITS - 43 SPACES FOR 129 UNITS	46 SPACES - 41 FULL - 5 COMPACT (46%)

OFF-STREET LOADING			
SECTION	DESCRIPTION	REQUIRED	PROPOSED
2101.1	OFF-STREET LOADING (APARTMENT HOUSE > 50 UNITS)	1 BERTH @ 55 FEET 1 SERVICE/DELIVERY @ 20 FEET 1 PLATFORM AREA @ 200 SF	1 BERTH @ 30 FEET 1 SERVICE/DELIVERY @ 20 FEET 1 PLATFORM AREA @ 200 SF


ROOF STRUCTURES			
SECTION	DESCRIPTION	REQUIRED	PROPOSED
411.3	NUMBER OF ROOF STRUCTURES	1 PERMITTED	2
411.5	HEIGHT OF ROOF STRUCTURES	SINGLE UNIFORM HEIGHT	VARIED (REFER TO DRAWINGS) - 12 FEET - 16 FEET

INCLUSIONARY ZONING			
SECTION	DESCRIPTION	PERMITTED	PROPOSED
	IZ MODIFICATIONS	4.2 FAR 80% LOT OCCUPANCY	4.06 FAR 79.5% RESIDENTIAL USE
2602.1	IZ APPLICABILITY	REQUIREMENTS APPLY	REQUIREMENTS TO BE MET
2603.1	IZ SET-ASIDE (RC OVERLAY)	50% OF FLOOR AREA ABOVE 40 FEET OF BUILDING HEIGHT	

GREEN AREA RATIO			
SECTION	DESCRIPTION	REQUIRED	PROPOSED
3401.2	GREEN AREA RATIO	0.30	REQUIREMENTS TO BE MET BY COMBINATION OF GREEN ROOF, TREES, AND SHRUBS WITHIN SITE BOUNDARIES

1711 Florida Avenue NW
Garage Reuse Concept Design

Zoning Analysis
June 3, 2014



1711 Florida Avenue NW
Garage Reuse Concept Design

Vicinity Map
June 3, 2014




Corner @ Florida Ave & Champlain Street NW



View From Champlain Street, Facing North



View from North @ Champlain Street



Adjacent Pepco Property

1711 Florida Avenue NW
Garage Reuse Concept Design

Site Photos
June 3, 2014



Townhomes along Florida Ave & V St



Florida Ave & Champlain St, Facing SE



PEPCO Facility along Champlain St



PEPCO Facility along Ontario Rd, Facing SW




Marie Reed Community Learning Center



Retail Along Florida Avenue

1711 Florida Avenue NW
Garage Reuse Concept Design


Context Photos
June 3, 2014



Note: The interior partition locations, and the number, size and location of residential units are preliminary. The final layouts may vary.

1711 Florida Avenue NW

Site Plan
June 3, 2014






Note: The interior partition locations, and the number, size and location of residential units are preliminary. The final layouts may vary.

1711 Florida Avenue NW

Basement Level with Existing
Parking Structure
June 3, 2014







Note: The interior partition locations, and the number, size and location of residential units are preliminary. The final layouts may vary.

1711 Florida Avenue NW

Ground Floor
June 3, 2014





Note: The interior partition locations, and the number, size and location of residential units are preliminary. The final layouts may vary.

1711 Florida Avenue NW


Typical Residential Floor
June 3, 2014



Note: The interior partition locations, and the number, size and location of residential units are preliminary. The final layouts may vary.

1711 Florida Avenue NW

Roof Deck
June 3, 2014





1711 Florida Avenue NW

South Elevation
June 3, 2014





1711 Florida Avenue NW

West Elevation
June 3, 2014





1711 Florida Avenue NW

Florida Ave Elevation
June 3, 2014






1711 Florida Avenue NW

Champlain Street Elevation
June 3, 2014

0 4' 8' 16' 32'
1/16"=1'-0" SCALE



1711 Florida Avenue NW

Building Section
June 3, 2014

