

SKYLAND TOWN CENTER

SPECIAL TREE REMOVALS & REPLACEMENTS

NO	TAG	BOTANICAL NAME	COMMON NAME	SIZE	CIRCUM	CONDITION	COMMENTS
				DBH			
1	801	Populus deltoides	Eastern Cottonwood	17.5	55.0	EXCELLENT	NATIVE, TO BE SAVED
2	802	Quercus rubra	Northern Red Maple	40.0	125.6	GOOD	NATIVE, TO BE SAVED
3	803	Liriodendron tulipifera	Tulip Poplar	24.5	76.9	GOOD	NATIVE, TO BE SAVED
4	804	Morus sp.	Mulberry	23.0	72.2	POOR	INVASIVE, TO BE REMOVED
5	805	Populus deltoides	Eastern Cottonwood	21.0	66.0	EXCELLENT	NATIVE, TO BE REMOVED
6	806	Ulmus pumila	Siberian Elm	32.2	101.1	GOOD	NON-NATIVE TO BE REMOVED
7	807	Robinia psuedoacacia	Black Locust	18.3	57.5	GOOD	NATIVE, TO BE REMOVED
8	808	Robinia psuedoacacia	Black Locust	19.0	59.7	GOOD	NATIVE, TO BE REMOVED
9	809	Ulmus pumila	Siberian Elm	18.3	57.5	GOOD	NON-NATIVE TO BE REMOVED
10	810	Ulmus pumila	Siberian Elm	20.8	65.3	GOOD	NON-NATIVE TO BE REMOVED
11	811	Robinia psuedoacacia	Black Locust	24.9	78.2	EXCELLENT	NATIVE, TO BE REMOVED
12	812	Populus deltoides	Eastern Cottonwood	19.2	60.3	EXCELLENT	NATIVE, TO BE REMOVED
13	813	Populus deltoides	Eastern Cottonwood	19.8	62.2	GOOD	NATIVE, TO BE REMOVED
14	814	Populus deltoides	Eastern Cottonwood	18.2	57.2	POOR	NATIVE, TO BE REMOVED
15	815	Liquidambar styraciflua	Sweetgum	18.5	58.1	POOR	NATIVE, TO BE REMOVED
16	816	Robinia psuedoacacia	Black Locust	18.9	59.3	GOOD	NATIVE, TO BE REMOVED
17	817	Robinia psuedoacacia	Black Locust	22.4	70.3	FAIR	NATIVE, TO BE REMOVED

Trees to be removed 14 - 3 (in POOR Condition) = 11

737.4

TOTAL Inch/Circum (Trees in Bold type not counted)

Average Replacement Size 3.5" Caliper =

10.9

TREE Inch/Circum

Required replacements 737.4 / 10.9 = 67.65

68

TOTAL REPLACEMENT TREES REQUIRED

Interior Street Trees shown on Town Center Plans (Not Required)

108

TOTAL SHOWN ON PLANS

EXHIBIT NO. 77

CASE NO. 09-03

ZONING COMMISSION
District of Columbia