Facsimile Cover Sheet

To: TAISIR RAZEQ
Company: ALTER CONSTRUCTION
PHONE: 703 937-7841
Fax: 703 319-1382

From: JOHN MARUT
Company: MARVIN WINDOW & DOOR SHOWPLACE COMMERCIAL
Phone: 703 536-3343
Fax: 703 536-3075

Date: 12/21/04
Pages including this cover page: 2

Comments: RE: MOLDAVIAN EMBASSY

PLEASE FIND ATTACHED THE PROPOSAL AS REQUESTED FOR THE ABOVE PROJECT.
IF YOU SHOULD HAVE ANY QUESTIONS PLEASE FEEL FREE TO CALL ME.

THANK YOU!

CELL # (571) 283-2418

BZA
Case No. 17384
Exhibit No. 8

Board of Zoning Adjustment
District of Columbia
CASE NO. 17384
EXHIBIT NO. 8

Dealer for Marvin
Windows and Doors

MARVIN
WINDOW & DOOR
SHOWPLACE INC.

December 21, 2004

To: Alter Construction
Phone: (703) 937-7841 Fax: (703) 319-1382

Attn: Taisir Razeq

Project: Moldavian Embassy

The Marvin Window & Door Showplace, Inc. proposes to furnish wood window units per the site survey performed on 12/10/04.

We include a labor alternate, materials, insurance, project management and shop drawings to perform the work specified in the documents provide.

Wood Windows:
Furnish & install (16) Marvin Showplace replicated sash installed, removal of vinyl window units, repair frames damaged when old sash were removed for the vinyl window installation, measure openings and make templates and ship for fabrication, install new sash in openings to include repairs of weights and cords damaged by others, furnish new parting beads and repair blind stops, install Lexan MR10 in lieu of glass, install new window stops, furnish and install sash locks and lifts, all units to be primed and painted.

Total Price: $ 61,500.00

Above prices are good for 45 days from the date of this proposal.

Terms:
Terms are a net thirty days from the date of the invoice, no exceptions taken.

Thank you, for this opportunity to be of service; we look forward to receiving your order.

Sincerely,

John G. Marut
Executive Vice President
Commercial Sales

I hereby accept this proposal:

Signature _____ Date _____

The window man

3853-A Pickett Road • Fairfax, Virginia 22031 • (703) 978-9888 • Fax (703) 978-1012

Razeq Saisir
Embassy of Molvova
2101 S St. N.W.
Washington, DC 20007

December 7, 2004

The Window Man
3853-A Pickett Rd.
Fairfax, VA 22031

Razeq

Here is the initial proposal for the replacement of 18 vinyl windows with 18 wood replacement windows, 16 will be with a radius type glass and 2 will be flat. The windows will be single hung with low e insulated glass. They will be manufactured by Wood Window Workshop using Spanish cedar, invisible block and tackle, solid brass sash locks, and primed painted. Installation will be by the Window Man, will caulk as necessary and haul away debris. All pricing is subject to Final Measurements and survey.

1. Cost of windows	78256
2. Labor to install	7200
Total	85,456

After Construction.

Razeq Taisir

Hamilton Smith

12/7/2004

THE WINDOW man
3853 A Pickett Road • Fairfax, VA 22031
(703) 978-9888

WRITTEN BY: Hamilton

BUDGET PROPOSAL

NAME Saisia, Razeq Embassy of Malvova DATE 12/7/04

Window/Door Style	Wood Single Hung		Radial		Rectangular FIXED
United Inches	117	101	103	123	73
Price Per Window/Door	4696	4618	4636	4722	1966
# of Windows/Doors: X	2	8	4	2	2
Subtotal	9392	36,944	18,544	9444	3932
Total Materials Price				78,256	

Labor Rate

18 x 400

x

Labor Price 7200

Options

1 Block & Tackle Balance
2 Brass Locks
3 Spanish Cedar primed
4
5

Total Price 85456
Option 1 Included
Option 2 Included
Option 3 Included
Option 4
Option 5
Grand Total 85,456

General Specs:

Remove Newly Windows & Install Replacement wood curved & Flat windows. Caulk as necessary. Haul away Debris. All pricing subject to final measurements.

Proposal Expires ~~xxx~~ 01/07/05