


BOARD OF ZONING ADJUSTMENT
District of Columbia

E NO. 17429
SIT NO. 941

EXISTING CONTOURS PLAN
1801 FOXHALL ROAD NW
SQUARE 1346, LOTS 3, 4, 801, 802 & 803
WASHINGTON - DISTRICT OF COLUMBIA

 MHG	Macris, Hendricks & Glascock, P.A. Engineers • Planners Landscape Architects • Surveyors		Proj. Mgr. SEC	Designer ABJ
	8220 Weyman Road, Suite 120 McLean, Virginia, Maryland 22106-1279		Date 09-06-05	Scale 1"=50'
Phone 301.670.0840 Fax 301.648.3033 www.mhga.com		Project No. 1998.306.12		
		Sheet 1 of 1		



2	06-06-06	Revised Roadway Improvements	SEC
1	02-21-06	Revised	SEC
NO.	DATE	DESCRIPTION	BY

CONCEPTUAL SITE UTILITY PLAN 1801 FOXHALL ROAD NW

SQUARE 1346, LOTS 3, 4, 801, 802 & 803

WASHINGTON - DISTRICT OF COLUMBIA



MHG Macris, Hendricks & Glascock, P.A.
Engineers • Planners
Landscape Architects • Surveyors

6220 Wilman Road, Suite 120
Montgomery Village, Maryland
20886-1279

Phone: 301.870.0840
Fax: 301.544.0803
www.mhga.com

Proj. Mgr.	Designer
SEC	SEC
Date	Scale
09-06-09	1"=50'
Project No.	Sheet
1999.306.12	1 of 1



VICINITY MAP
SCALE 1" = 2,000'
COPYRIGHT 1994 BY ADC OF ALEXANDRIA, INC.
PERMITTED USE NO. 001010

NOTES

- Grading is conceptual and subject to refinement at final engineering.
- Location and size of retaining walls are conceptual and subject to refinement at final engineering. Additional retaining walls may be required on individual lots. Retaining wall along the boundary with the National Park Service Land will be located a minimum of 10' from the park boundary.
- Street widths to be 28' curb to curb, with two travel lanes and parking on one side or 22' curb to curb, with two travel lanes only. The exact location of each will be determined at final engineering.
- Lot configurations and dimensions and street alignments subject to minor adjustments at final engineering.
- House footprints shown on individual lots are conceptual and are subject to change.

NO.	DATE	DESCRIPTION	BY
2	06-08-06	Revised Roadway Improvements	SEC
1	02-21-06	Revised	SEC

CONCEPTUAL SITE DEVELOPMENT PLAN 1801 FOXHALL ROAD NW

SQUARE 1346, LOTS 3, 4, 801, 802 & 803

WASHINGTON - DISTRICT OF COLUMBIA



Macris, Hendricks & Glascock, P.A.
Engineers • Planners
Landscape Architects • Surveyors

8220 Wagon Road, Suite 120
Montgomery Village, Maryland
20895-1279

Phone: 301.875.0800
Fax: 301.848.0802
www.mhga.com

Proj. Mgr.	Designer
SEC	JAR
Date	Scale
09-06-05	1"=50'
Project No.	Sheet
1998.306.12	1 of 1

SCHOOL SWM
FACILITY
D.A. = 5 Ac.

STRUCTURAL
BIORETENTION
FACILITIES TO BE
PROVIDED WITHIN
REAR LOT AREAS

NORTHEAST SWM
FACILITY
D. A. = 1.5 Ac.



STORMWATER MANAGEMENT SUMMARY 1801 FOXHALL ROAD N.W.

Onsite stormwater management (SWM) is to be provided by four underground vaults and a limited number of bioretention inlets which will detain and filter storm runoff from the proposed school and residential developments. There are two vaults proposed for the residential project. These have been named the Northeast (NE) and the Southeast (SE) SWM Facility. The other two vaults provide runoff management for the proposed school and have been named the School SWM Facility and the Athletic Field SWM Facility.

All of the vaults will include sand filters or filter cartridges for water quality stormwater management plus 2-year and 15-year stormwater quantity management. The sizing of the filters and the design of the 2-year and 15-year quantity control are to be done in accordance with the Stormwater Management Guidebook by the District of Columbia, Department of Health Watershed Protection Division. In addition, extended detention of the 1 year 24 hour storm event is to be provided by the vaults to control downstream channel erosion. This level of quantity stormwater management is prescribed by the State of Maryland and is considered state of the art. The outlets from the vaults will be designed to promote sheet flow to minimize the potential for downstream erosion. Outlet options include riprap areas top soiled and seeded with a native plant mix and "joint planted" with native trees and/or live stakes, plunge pools, and splitting outfalls into multiple release points. A large storm overflow pipe is proposed for the Athletic Field SWM Facility to limit the amount of runoff that is discharged toward Whitehaven Park. This pipe will direct excess large storm runoff (greater than 15 year events) toward the southeast.

Runoff from small portions of the site drains from the rear of a few of the proposed residential lots to Whitehaven Park and to Hoban Road. For these areas of the site, Filterra or similar devices are proposed to provide water quality control. Runoff that drains to Hoban Road is conveyed by an extensive separate public storm drain system that extends underground through Glover Archibald Park. It may also be possible to utilize this existing public storm drain system to receive runoff from additional portions of the property. This will be explored at final engineering.

SOUTHEAST SWM
FACILITY
D.A. = 5.5 Acres

ATHLETIC FIELD
SWM FACILITY
D.A. = 2.3 Ac.

LARGE STORM
OVERFLOW PIPE

STRUCTURAL
BIORETENTION
FACILITY

NO.	DATE	DESCRIPTION	BY
3	06-06-06	Revised Roadway Improvements	SEC
2	05-31-06	Added Athletic Field By-Pass	SEC
1	02-21-06	Revised	SEC

CONCEPTUAL STORM DRAIN AND SWM PLAN 1801 FOXHALL ROAD NW

SQUARE 1346, LOTS 3, 4, 801, 802 & 803

WASHINGTON - DISTRICT OF COLUMBIA



Macris, Hendricks & Glascock, P.A.
Engineers • Planners
Landscape Architects • Surveyors


8220 Wigmore Road, Suite 120
Manassas Park, Virginia 20108-1270

Phone 201.679.0845
Fax 201.643.0893
www.mhga.com


Proj. Mgr. SEC	Designer SDR
Date 09-06-06	Scale 1"=50'
Project No. 1998.306.11	Sheet 1 of 2




ATHLETIC FIELD
SWM FACILITY
Scale 1" = 30'



SCHOOL SWM FACILITY
Scale 1" = 30'



SOUTHEAST SWM FACILITY
Scale 1" = 30'



NORTHEAST SWM FACILITY
Scale 1" = 30'

NO.	DATE	DESCRIPTION	BY
3	06-08-06	Revised Roadway Improvements	SEC
2	05-31-06	Added Athletic Field By-Pass	SDH
1	02-21-06	Revised	SDH

CONCEPTUAL STORM DRAIN AND SWM PLAN
1801 FOXHALL ROAD

SQUARE 1346, LOTS 3, 4, 801, 802 & 803

WASHINGTON - DISTRICT OF COLUMBIA



Macris, Hendricks & Glascock, P.A.
Engineers • Planners
Landscape Architects • Surveyors

1020 Virginia Road, Suite 120
Montgomery Village, Maryland
20894-1274

Phone: 301.470.0840
Fax: 301.648.0803
www.mhga.com

Proj. Mgr.	Designer
SEC	SDH
Date	Scale
09-06-05	1"=30'
Project No.	Sheet
1999.306.11	2 of 2

