

REQUIRED VERIFICATION AND INSPECTION OF STRUCTURAL STEEL CONSTRUCTION

VERIFICATION AND INSPECTION	REFERENCED STANDARD	IBC REFERENCE
1. SPECIAL INSPECTION FOR STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH THE QUALITY ASSURANCE INSPECTION REQUIREMENTS OF AISC 360.	AISC 360-10: CHAPTER N	1705.2.1

REQUIRED VERIFICATION AND INSPECTION OF MASONRY CONSTRUCTION

VERIFICATION AND INSPECTION	REFERENCED STANDARD	IBC REFERENCE
1. MASONRY CONSTRUCTION SHALL BE INSPECTED AND VERIFIED IN ACCORDANCE WITH TMS 402/ACI 530/ASCE 5 AND TMS 602/ACI 530.1/ASCE 6 QUALITY ASSURANCE PROGRAM REQUIREMENTS.	ACI 530-11	1705.4

REQUIRED VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION

VERIFICATION AND INSPECTION	CONTINUOUS	PERIODIC	REFERENCED STANDARD	IBC REFERENCE
1. INSPECTION OF REINFORCING STEEL INCLUDING PRESTRESS TENDONS AND PLACEMENT.	---	X	ACI 318.3.5, 7.1-7.7	1910.4
2. INSPECTION OF REINFORCING STEEL WELDING IN ACCORDANCE WITH TABLE 1704.3, ITEM 5B.	---	---	AWS D1.4, ACI 318: 3.5.2	---
3. INSPECTION OF ANCHORS CAST IN CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED OR WHERE STRENGTH DESIGN IS USED.	---	X	ACI 318: 8.1.3, 21.2.8	1908.5, 1909.1
4. INSPECTION OF ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS.	---	X	ACI 318: 3.8.6, 8.1.3, 21.2.8	1909.1
5. VERIFYING USE OF REQUIRED DESIGN MIX.	----	X	ACI 318: Ch. 4, 5.2-5.4	1904.2, 1910.2, 1910.3
6. AT THE TIME FRESH CONCRETE IS SAMPLED TO FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.	X	---	ASTM C 172, ASTM C 31	1910.10
7. INSPECTION OF CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.	X	---	ACI 318: 5.9, 5.10	1910.6, 1910.7, 1910.8
8. INSPECTION FOR MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES.	---	X	ACI 318: 5.11-5.13	1910.9
9. VERIFICATION OF IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS.	---	X	ACI 318: 6.2	---
10. INSPECT FORMWORK FOR SHAPE, LOCATIONS AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.	---	X	ACI 318: 6.1.1	---

REQUIRED VERIFICATION AND INSPECTION OF STEEL CONSTRUCTION OTHER THAN STRUCTURAL STEEL

VERIFICATION AND INSPECTION	CONTINUOUS	PERIODIC	REFERENCED STANDARD
1. MATERIAL VERIFICATION OF COLD-FORMED STEEL DECK:			
a. IDENTIFICATION MARKING TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	---	X	APPLICABLE ASTM MATERIAL STANDARDS
b. MANUFACTURER'S CERTIFIED TEST REPORTS.	---	X	---
2. INSPECTION OF WELDING:			
a. COLD-FORMED STEEL DECK:			
1) FLOOR AND ROOF DECK WELDS.	---	X	AWS D1.3
b. REINFORCING STEEL:			
1) VERIFICATION OF WELDABILITY OF REINFORCING STEEL OTHER THAN ASTM A 706.	---	X	AWS D1.4, ACI 318: 3.5.2
2) REINFORCING STEEL RESISTING FLEXURAL AND AXIAL FORCES IN INTERMEDIATE AND SPECIAL MOMENT FRAMES, AND BOUNDARY ELEMENTS OF SPECIAL REINFORCED CONCRETE SHEAR WALLS AND SHEAR REINFORCEMENT.	X	---	AWS D1.4, ACI 318: 3.5.2
3) SHEAR REINFORCEMENT.	X	---	AWS D1.4, ACI 318: 3.5.2
4) OTHER REINFORCING STEEL.	---	X	AWS D1.4, ACI 318: 3.5.2

REQUIRED VERIFICATION AND INSPECTION OF CAST-IN-PLACE DEEP FOUNDATION ELEMENTS

VERIFICATION AND INSPECTION	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED
1. OBSERVE DRILLING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH ELEMENT.	X	---
2. VERIFY PLACEMENT LOCATIONS AND PLUMBNESS, CONFIRM ELEMENT DIAMETERS, BELL DIAMETERS (IF APPLICABLE), LENGTHS, EMBEDMENT INTO BEDROCK (IF APPLICABLE) AND ADEQUATE END-BEARING STRATA CAPACITY, RECORD CONCRETE OR GROUT VOLUMES.	X	---
3. FOR CONCRETE ELEMENTS, PERFORM ADDITIONAL INSPECTIONS IN ACCORDANCE WITH SECTION 1705.3.	---	---

HATCHING INDICATES SUPPLEMENTAL INFORMATION THAT IS EXCLUDED FROM FOUNDATION TO GRADE PACKAGE

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesai - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 DC Water Review - Valid Elward - 08-23-2019

DCRA APPROVAL STAMP




2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037
 202 298 6700
 WWW.QUINNEVANS.COM

Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002
 QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00



FOUNDATION TO GRADE
 03/03/17

NO.	DESCRIPTION	DATE

S0030
 Board of Zoning Adjustment
 CASE NO. 201911
 EXHIBIT NO. 444A

**SLAB/SLAB-ON-GRADE REINFORCEMENT
LAP SPLICE LENGTH SCHEDULE (INCHES)**

BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION (LTS)					
		f _c = 3 KSI	f _c = 4 KSI	f _c = 5 KSI	f _c = 6 KSI	f _c = 7 KSI	f _c = 8 KSI
#4	5.500	22	19	17	16	14	14
#5	5.375	32	28	25	23	21	20
#6	5.250	43	37	34	31	28	27
#7	5.125	69	60	54	49	46	43
#8	5.000	86	74	67	61	56	53

**COLUMN REINFORCEMENT
LAP SPLICE LENGTH SCHEDULE (INCHES)**

BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION (LTS)									COMPRESSION (LCS)
		f _c = 4 KSI	f _c = 5 KSI	f _c = 6 KSI	f _c = 7 KSI	f _c = 8 KSI	f _c = 9 KSI	f _c = 10 KSI	f _c = 11 KSI	f _c = 12 KSI	
#5	2.125	28	25	23	21	20	19	18	18	18	19
#6	2.250	37	34	31	28	27	25	24	24	24	23
#7	2.375	54	49	45	41	39	36	35	35	35	27
#8	2.500	62	56	51	47	44	42	39	39	39	30
#9	2.875	70	63	57	53	50	47	44	44	44	34
#10	3.250	79	71	64	60	56	53	50	50	50	39
#11	3.625	87	78	71	66	62	58	55	55	55	43

**GRADE BEAM/BEAM REINFORCEMENT
LAP SPLICE LENGTH SCHEDULE (INCHES)**

BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION (LTS)													
		f _c = 4 KSI		f _c = 5 KSI		f _c = 6 KSI		f _c = 7 KSI		f _c = 8 KSI		f _c = 9 KSI		f _c = 10 KSI	
		TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER
#4	1.500	33	25	29	23	27	21	25	19	23	18	22	17	21	16
#5	1.625	41	31	36	28	33	26	31	24	29	22	27	21	26	20
#6	1.750	49	37	44	34	40	31	37	28	35	27	33	25	31	24
#7	1.875	71	54	63	49	58	45	54	41	50	39	47	36	45	35
#8	2.000	81	62	72	56	66	51	61	47	57	44	54	42	51	39
#9	2.375	91	70	81	63	74	57	69	53	64	50	61	47	58	44
#10	2.625	102	79	92	71	84	64	77	60	72	56	68	53	65	50
#11	2.875	114	87	102	78	93	71	86	66	80	62	76	58	72	55

**FOOTING/MAT REINFORCEMENT
LAP SPLICE LENGTH SCHEDULE (INCHES)**

BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION LAP (LTS)													
		f _c = 4 KSI		f _c = 5 KSI		f _c = 6 KSI		f _c = 7 KSI		f _c = 8 KSI		f _c = 9 KSI		f _c = 10 KSI	
		TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER	TOP BARS	OTHER
#4	5.500	20	15	18	14	16	13	15	12	14	12	13	12	13	12
#5	5.375	25	19	22	17	20	16	19	14	18	14	17	13	16	12
#6	5.250	29	23	26	20	24	19	22	17	21	16	20	15	19	15
#7	5.125	43	33	38	29	35	27	32	25	30	23	29	22	27	21
#8	5.000	49	37	44	34	40	31	37	28	35	27	33	25	31	24
#9	4.875	63	49	57	44	52	40	48	37	45	35	42	33	40	31
#10	4.750	82	63	74	57	67	52	62	48	58	45	55	42	52	40
#11	4.625	104	80	93	72	85	65	79	61	74	57	69	54	66	51

**Shear Wall Reinforcement - Vertical Bars
Lap Splice Length Schedule (Inches)**

BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION (LTS)									COMPRESSION (LCS)
		f _c = 4 KSI	f _c = 5 KSI	f _c = 6 KSI	f _c = 7 KSI	f _c = 8 KSI	f _c = 9 KSI	f _c = 10 KSI	f _c = 11 KSI	f _c = 12 KSI	
#4	5.500	15	14	13	12	12	12	12	12	12	15
#5	5.375	19	17	16	14	14	13	12	12	12	19
#6	5.250	26	23	21	20	19	18	17	17	17	23
#7	5.125	42	38	35	32	30	28	27	27	27	27
#8	5.000	53	48	44	40	38	36	34	34	34	30
#9	4.875	65	59	53	50	46	44	42	42	42	34
#10	4.750	80	71	65	60	56	53	51	51	51	39
#11	4.625	95	85	77	72	67	63	60	60	60	43

**Shear Wall Reinforcement - Horizontal Bars
Lap Splice Length Schedule (Inches)**


BAR SIZE	MINIMUM BAR SPACING (INCHES)	TENSION (LTS)									COMPRESSION (LCS)
		f _c = 4 KSI	f _c = 5 KSI	f _c = 6 KSI	f _c = 7 KSI	f _c = 8 KSI	f _c = 9 KSI	f _c = 10 KSI	f _c = 11 KSI	f _c = 12 KSI	
#4	5.500	25	22	20	19	18	17	16	16	16	15
#5	5.375	36	32	29	27	26	24	23	23	23	19
#6	5.250	49	44	40	37	35	33	31	31	31	23
#7	5.125	78	70	64	59	55	52	50	50	50	27
#8	5.000	97	87	79	73	69	65	61	61	61	30
#9	4.875	117	105	96	89	83	78	74	74	74	34
#10	4.750	141	126	115	106	100	94	89	89	89	39
#11	4.625	165	147	135	125	117	110	104	104	104	43

DEVELOPMENT LENGTH SCHEDULE (INCHES)

BAR SIZE	MINIMUM BAR SPACING (INCHES) [MAX(1* db) + db] NOTE 2	TENSION												COMPRESSION															
		NOTED AS Ld ON DRAWINGS						NOTED AS Ldh ON DRAWINGS						NOTED AS Ldc ON DRAWINGS															
		f _c (PSI)						f _c (PSI)						f _c (PSI)															
		3000	4000	5000	7000	8000	10,000	3000	4000	5000	7000	8000	10,000	3000	4000	5000	7000	8000	10,000										
#4	1.500	22	19	17	16	15	14	13	12	12	12	11	10	9	8	8	7	6	6	6	11	10	9	9	9	9	9	9	9
#5	1.625	28	24	22	20	18	17	16	15	15	15	14	12	11	10	9	8	8	8	8	8	14	12	12	12	12	12	12	12
#6	1.750	33	29	26	24	22	21	19	18	18	18	17	15	13	12	11	10	9	9	9	17	15	14	14	14	14	14	14	14
#7	1.875	48	42	38	34	32	30	28	27	27	27	27	20	17	15	14	13	12	12	11	11	11	20	17	16	16	16	16	16
#8	2.000	55	48	43	39	36	34	32	30	30	30	30	22	19	17	16	15	14	13	12	12	12	22	19	18	18	18	18	18
#9	2.375	62	54	48	44	41	38	36	34	34	34	34	25	22	20	18	17	16	15	14	14	14	25	22	21	21	21	21	21
#10	2.625	70	61	54	50	46	43	41	39	39	39	39	28	25	22	20	19	18	17	16	16	28	25	23	23	23	23	23	23
#11	2.875	78	67	60	55	51	48	45	43	43	43	43	31	27	24	22	21	19	18	17	17	31	27	26	26	26	26	26	26

DEVELOPMENT LENGTH SCHEDULE NOTES:
 1. WHERE MORE THAN 12 INCHES OF FRESH CONCRETE IS CAST BELOW THE DEVELOPMENT LENGTH, MULTIPLY Ld BY 1.3.
 2. WHERE STIRRUPS OR TIES ARE NOT PRESENT THROUGHOUT Ld, MINIMUM BAR SPACING MUST BE INCREASED TO [MAX(1* db) + 2db] FOR SCHEDULED VALUES TO BE APPLICABLE.

LAP SPLICE NOTES:

- TABULATED VALUES ARE PER ACI 318-11 REQUIREMENTS FOR NORMALWEIGHT CONCRETE. THE VALUES ON THIS SHEET DO NOT APPLY TO LIGHTWEIGHT CONCRETE.
- SEE TYPICAL DETAILS FOR CLEAR COVER.
- MINIMUM BAR SPACING DIAGRAM - "S"

 - FIRST BAR
 - SECOND BAR PLACED OR SPLICE BAR
- WHERE ACTUAL CONDITIONS DIFFER FROM THE CLEAR COVER SHOWN ON THE TYPICAL DETAILS OR DIFFER FROM PROVIDED SCHEDULED BAR SIZE, MINIMUM SPACING AND/OR f_c LENGTHS SHALL BE ADJUSTED ONLY WITH THE APPROVAL OF THE STRUCTURAL ENGINEER OF RECORD.
- TABULATED VALUES ARE FOR NON-EPOXY COATED, GRADE 60 REINFORCEMENT IN NORMALWEIGHT CONCRETE.
 FOR EPOXY COATED REINFORCEMENT:
 MULTIPLY Ld BY 1.5
 MULTIPLY Ldh BY 1.2
 Ldc IS NOT AFFECTED
 MULTIPLY LTS BY 1.3 FOR "TOP BARS"
 MULTIPLY LTS BY 1.5 FOR ALL OTHER REINFORCEMENT
 FOR GRADE 75 REINFORCEMENT:
 MULTIPLY Ld, Ldh, Ldc, AND LTS BY 1.25
 MULTIPLY Lcs BY 1.45
- WHERE BARS OF DIFFERENT SIZES ARE LAP SPLICED IN TENSION, THE TENSION LAP SPLICE LENGTH (LTS) SHALL BE THE LARGER OF THE TENSION DEVELOPMENT LENGTH (Ld) OF THE LARGER BAR AND THE TENSION LAP SPLICE LENGTH OF THE SMALLER BAR.
- WHERE BARS OF DIFFERENT SIZES ARE LAP SPLICED IN COMPRESSION, THE COMPRESSION LAP LENGTH (LCS) SHALL BE THE LARGER OF THE COMPRESSION DEVELOPMENT LENGTH (Ldc) OF THE LARGER BAR OR THE COMPRESSION LAP SPLICE LENGTH OF THE SMALLER BAR.
- "TOP BARS" ARE DEFINED AS HORIZONTAL REINFORCEMENT PLACED SUCH THAT MORE THAN 12 INCHES OF FRESH CONCRETE IS CAST BELOW THE DEVELOPMENT LENGTH OR SPLICE. "OTHER BARS" ARE ALL BARS FOR WHICH THIS DOES NOT APPLY.

GOVERNMENT OF THE DISTRICT OF COLUMBIA
 PERMIT OPERATIONS DIVISION
 PLANS APPROVED
 Permit No. FD1800040 Date 08/23/19

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Eilon Debesari - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 Water Review - Vahid Shavari - 08-23-2019

DCRA APPROVAL STAMP

QUINN EVANS ARCHITECTS

2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037

202 298 6700
 WWW.QUINNEVANS.COM


Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00

LAP SPLICE SCHEDULES



FOUNDATION TO GRADE
 03/03/17

REVISIONS

NO.	DESCRIPTION	DATE

S0300

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesai - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 DW Water Review - Vahid Elvandi - 08-23-2019

DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037

202 298 6700
 WWW.QUINNEVANS.COM


Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00


2ND FLOOR AND ENTRY LEVEL FRAMING PLAN



FOUNDATION TO GRADE
 03/03/17

NO.	DESCRIPTION	DATE

S1020



BOTTOM BAR REINFORCEMENT LEGEND
 NOT TO SCALE

- NUMBER / SIZE / LENGTH OF BARS SHOWN IN ONE DIRECTION ONLY SAME NOTATIONS APPLY IN PERPENDICULAR DIRECTION
- CENTERLINE OF COLUMN MAY NOT COINCIDE W/ GRIDLINES SEE DRAWINGS FOR OFFSET DIMENSION
- PLACE ADDITIONAL BARS AT SAME SPACING OF CONTINUOUS BARS AND MIDWAY BETWEEN CONTINUOUS BARS UON
- ALL CONTINUOUS BOTTOM BARS TO EXTEND WITHIN 2 INCHES OF SLAB EDGE
- A MINIMUM OF 2 BOTTOM BARS MUST EXTEND THROUGH THE COLUMN JOINT IN EACH DIRECTION
- AT EXTERIOR SUPPORT HOOK 2 BOTTOM BARS THAT PASS THROUGH COLUMN WITH 90° STANDARD HOOK OR IF NECESSARY USE 180° STANDARD HOOK



TWO-WAY SLAB BOTTOM BAR REINFORCEMENT LEGEND
 NOT TO SCALE

- SHEET NOTES:**
- TOP OF SLAB AND TOP OF BEAM EL. 170'-0" UON THUS:
 - X⁺ - INDICATES CHANGE IN STRUCTURAL SLAB ELEVATION
 - SLABS TO BE THICK NORMALWEIGHT CONCRETE TWO-WAY SLAB WITH DROP PANELS, TYPICAL UON
 - SEE GENERAL NOTES FOR CONCRETE COMPRESSIVE STRENGTH
 - SEE DRAWING FOR SLAB REINFORCEMENT
 - FOR ADDITIONAL INFORMATION REFER TO THE FOLLOWING DRAWINGS:

DRAWING LISTS, GENERAL NOTES AND LOADING DIAGRAMS	S0 SERIES DRAWINGS
TYPICAL FOUNDATION DETAILS	S2 SERIES DRAWINGS
LATERAL SYSTEM ELEVATIONS, CONNECTION FORCES AND DETAILS	S3 SERIES DRAWINGS
CONCRETE SUPERSTRUCTURE SCHEDULES AND DETAILS	S4 SERIES DRAWINGS
STEEL SUPERSTRUCTURE SCHEDULES AND DETAILS	S5 SERIES DRAWINGS
MASONRY DETAILS	S6 SERIES DRAWINGS
 - SYMBOLS:
 - Y⁻ INDICATES ONE-WAY SLAB Y⁻ THICK AND SPAN DIRECTION
 - SX INDICATES ONE-WAY SLAB SPAN DIRECTION SEE ONE-WAY SCHEDULE AND ONE-WAY SLAB DETAILS
 - UP INDICATES SLOPE IN TOP OF SLAB
 - NOTATIONS:
 - CA / CB INDICATES COLUMN ABOVE / BELOW
 - DB INDICATES ELEVATOR DIVIDER BEAM (NOT FIREPROOFED)
 - TR INDICATES COLUMN FROM ABOVE TRANSFERS

REINFORCEMENT PLAN NOTES:


- SEE DRAWING SX-XXX FOR FRAMING PLAN
- SLAB BOTTOM BAR CLEAR COVER X"
- SLAB TOP BAR CLEAR COVER
- T/SLAB ELEVATION SEE FRAMING PLAN
- TWO-WAY SLAB BAR PLACEMENT:
 - DIRECTION OUTER LAYER
 - DIRECTION INNER LAYER
- ONE-WAY SLAB BAR PLACEMENT:
 - TOP AND BOTTOM BARS PARALLEL TO SPAN DIRECTION
 - SHRINKAGE AND TEMPERATURE BARS PERPENDICULAR TO SPAN DIRECTION
- SEE TYPICAL SLAB DETAILS
- FOR COLUMN STRIP WIDTH SEE TOP BARS LEGEND
- FOR SLAB CORNERS SUPPORTED BY BEAMS OR WALLS, SEE TYPICAL BEAM / WALL SUPPORTED SLAB EXTERIOR CORNER DETAIL
- SR-X INDICATES STUDRAIL. SEE STUDRAIL DETAILS



TOP BAR REINFORCEMENT LEGEND

- NUMBER/SIZE/LENGTH OF MIDDLE STRIP BARS SHOWN IN ONE DIRECTION ONLY SAME NOTATION APPLIES IN PERPENDICULAR DIRECTION
- CENTERLINE OF COLUMN MAY NOT COINCIDE W/ GRIDLINES SEE DRAWINGS FOR OFFSET DIMENSION
- HOOK ALL TOP BARS THAT PASS THROUGH COLUMN AT EXTERIOR SUPPORT WITH 90° STANDARD HOOK OR IF NECESSARY USE 180° STANDARD HOOK

TWO-WAY SLAB TOP BAR REINFORCEMENT LEGEND
 NOT TO SCALE



3/8/2017 11:42:58 PM
 P:\DCR\Projects\2018\03\DCR\Drawings\20180303\F10.dwg
 P:\DCR\Projects\2018\03\DCR\Drawings\20180303\F10.dwg
 P:\DCR\Projects\2018\03\DCR\Drawings\20180303\F10.dwg

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Eilon Debesas - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 SW Water Review - Vahid Shariati - 08-23-2019

DCRA APPROVAL STAMP



QUINN EVANS ARCHITECTS

2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037

202 298 6700
 WWW.QUINNEVANS.COM

Thornton Tomasetti


Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00


TYPICAL GRADE BEAM DETAILS




FOUNDATION TO GRADE
 03/03/17

REVISIONS		
NO.	DESCRIPTION	DATE


S2050




2 GRADE BEAM SECTION - BASE SHEAR TRANSFER CONDITION
 NOT TO SCALE




GRADE BEAM - CORNER CONDITION




8 GRADE BEAM STIRRUP TYPES
 NOT TO SCALE



10 TYPICAL GRADE BEAM SLEEVE - ELEVATION
 NOT TO SCALE




1 TYPICAL GRADE BEAM ELEVATION
 NOT TO SCALE




GRADE BEAM - T-INTERSECTION
GRADE BEAM - INTERIOR INTERSECTION

4 TYPICAL GRADE BEAM INTERSECTION PLAN DETAILS
 NOT TO SCALE



6 CAISSON CAP AT GRADE BEAM - PLAN
 NOT TO SCALE



5 TYPICAL GRADE BEAM INTERIOR INTERSECTION DETAIL
 NOT TO SCALE

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Bilal Debesay - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE G&R Review - Nykia Barnes - 08-23-2019
 DC Water Review - Vahid Shvardi - 08-23-2019

DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037
 202 298 6700
 WWW.QUINNEVANS.COM

Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

**MCMILLAN
 COMMUNITY
 CENTER**

2940 N Capitol St, NW
 Washington, DC
 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00


**FOUNDATION
 SECTIONS
 AND
 DETAILS**



FOUNDATION TO GRADE
 03/03/17

NO.	DESCRIPTION	DATE

S2100



1 SECTION AT EDGE OF SWIMMING POOL
 1/2" = 1'-0"

2 SECTION AT NORTH RETAINING WALL
 1/4" = 1'-0"

3 SECTION AT WEST RETAINING WALL
 3/8" = 1'-0"

08/23/19 14:52 PM
 P:\DCR\Projects\2018\03\DCR\Drawings\2018\03\08_FTD
 Permit\FD1800040_MCMillan_Community_Ctr

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Eilon Debesari - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 DC Water Review - Vahid Shihadi - 08-23-2019

DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037
 202 298 6700
 WWW.QUINNEVANS.COM


Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC
 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00


TYPICAL CONCRETE COLUMN DETAILS



FOUNDATION TO GRADE
 03/03/17

NO.	DESCRIPTION	DATE

S4010



08/23/19 11:43:58 PM
 C:\Users\jhammond\OneDrive\Documents\Projects\2017\0308.FTD
 Permit\FD1800040_MCMILLAN_Community_Ctr

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesai - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 DW Water Review - Vahid Elvandi - 08-23-2019

DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037

202 298 6700
 WWW.QUINNEVANS.COM

Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00

TYPICAL CONCRETE BEAM DETAILS










FOUNDATION TO GRADE
 03/03/17

REVISIONS

NO.	DESCRIPTION	DATE

S4030



These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesari - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 Water Review - Vahid Shavari - 08-23-2019

DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037

202 298 6700
 WWW.QUINNEVANS.COM

Thornton Tomasetti

Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00

TYPICAL CONCRETE SLAB DETAILS




FOUNDATION TO GRADE
 03/03/17


REVISIONS

NO.	DESCRIPTION	DATE


S4040



- NOTES:**
- REFER TO PLANS FOR ADDITIONAL BARS AROUND OPENINGS
 - SEE STRUCTURAL DRAWINGS FOR QUANTITY AND LOCATIONS OF OPENINGS. CONTRACTOR SHALL VERIFY SIZE AND LOCATION OF ALL OPENINGS WITH MEP DRAWINGS NOTIFY STRUCTURAL ENGINEER IN WRITING OF ANY DISCREPANCIES FOR REVIEW AND APPROVAL
 - FOR TWO-WAY SLAB SEE TYPICAL TWO-WAY SLAB OPENING LIMITATIONS. FOR OPENING NOT MEETING LIMITATIONS OR GREATER THAN 3 FEET, SUBMIT OPENINGS TO SER FOR APPROVAL
 - FOR ONE-WAY SLABS WHERE THE OPENING DIMENSION PERPENDICULAR TO THE DIRECTION OF THE SPAN IS GREATER THAN 2 FEET, SUBMIT OPENINGS TO SER FOR APPROVAL
 - WHERE ADJACENT OPENINGS ARE NOT SEPARATED BY 2X THE LARGEST OPENING DIMENSION OR WOULD INTERRUPT THE ADDITIONAL REINFORCEMENT FROM THE ADJACENT OPENING, SUBMIT OPENINGS TO SER FOR APPROVAL




- ADDITIONAL BARS WHERE BARS ARE INTERRUPTED**
- NOTES: ADDITIONAL BARS**
- PROVIDE ADDITIONAL BARS ON EACH SIDE OF OPENING FOR TOP AND BOTTOM BARS THAT ARE INTERRUPTED BY OPENINGS. DISTRIBUTE REPLACEMENT BARS EQUALLY TO BOTH SIDES OF OPENING AT 3" SPACING
 - PROVIDE A MINIMUM OF 2 BARS EACH SIDE OF OPENING TOP AND BOTTOM WHERE NO TOP BARS ARE PRESENT, PROVIDE ADDITIONAL TOP BARS SHOWN ABOVE
 - AT CLUSTERED OPENINGS, PROVIDE THESE ADDITIONAL BARS AROUND THE CLUSTER PLUS THE ADDITIONAL BARS SHOWN IN THE CLUSTERED OPENING DETAIL






ADDITIONAL TOP BARS


OPENING SIZE (LARGER DIMENSION OF OPENING)	TOP BARS ALL SIDES
0 - 12"	NONE
12" - 36"	(1) #4



- CLUSTERED OPENING ADDITIONAL REINFORCEMENT**
- NOTES: CLUSTERED OPENINGS**
- THE REINFORCEMENT REQUIREMENTS AT CLUSTERED OPENINGS ARE IN ADDITION TO THE TYPICAL SLAB OPENING DETAIL REQUIREMENTS AROUND THE ENTIRE CLUSTER
 - FOR ONE-WAY SLABS, WHEN CLUSTERED OPENING IS GREATER THAN 2 FEET, SUBMIT TO SER FOR APPROVAL.
 - FOR TWO-WAY SLABS, WHEN CLUSTERED OPENING DOES NOT MEET TWO-WAY SLAB OPENING LIMITATIONS OR IS GREATER THAN 3 FEET, SUBMIT TO SER FOR APPROVAL




- NOTES:**
- CONTRACTOR SHALL SUBMIT CONSTRUCTION JOINT LAYOUT PLAN FOR SER APPROVAL
 - FOR SLAB REINFORCEMENT NOT SHOWN, SEE PLAN OR SCHEDULE





CURB DIMENSION AND REINFORCEMENT SCHEDULE



W	H	X@Y"	Z"





- POST-TENSIONED CONCRETE NOTES:**
- FOR POST-TENSIONED CONCRETE, MAXIMUM CONDUIT OUTER DIAMETER IS THE SMALLER OF:
 - T/4
 - 2"
 - CONDUITS MAY NOT BE TIED TO, CONTACT, DISPLACE, OR INTERRUPT THE POST-TENSIONING REINFORCEMENT
 - MAINTAIN A CLEAR SPACING BETWEEN TENDONS AND CONDUITS OF THREE TIMES THE DIAMETER OF THE CONDUIT BUT NOT LESS THAN 6 INCHES



- NOTES:**
- FOR SIZE AND LOCATION SEE ARCH, MEP, OR STRUCTURAL DRAWINGS
 - ROUGHEN SURFACE OF SLAB TO 1/4" AMPLITUDE CLEAN THOROUGHLY AND APPLY BONDING AGENT IMMEDIATELY BEFORE CASTING CURB
 - THIS DETAIL IS APPLICABLE TO CURBS SUPPORTING EXTERIOR WALLS. SEE ADDITIONAL DETAILS FOR CURTAIN WALL SUPPORT. SEE ARCH DRAWINGS FOR EMBEDDED PLATES AND BLOCKOUTS
 - SEE ARCH DRAWINGS FOR EMBEDDED PLATES AND BLOCKOUTS. REPLACE REINFORCEMENT INTERRUPTED BY BLOCKOUTS
 - AT CONTRACTORS OPTION DRILLED-IN DOWELS WITH ADHESIVE ANCHORS MAY BE PERMITTED BAR SIZE AND SPACING MAY CHANGE DEPENDING ON EMBEDMENT REQUIRED CONTRACTOR TO VERIFY WITH SER



- NOTES:**
- FOR SIZE AND LOCATION SEE ARCH, MEP, OR STRUCTURAL DRAWINGS
 - ROUGHEN SURFACE OF SLAB TO 1/4" AMPLITUDE CLEAN THOROUGHLY AND APPLY BONDING AGENT IMMEDIATELY BEFORE CASTING CURB
 - THIS DETAIL IS APPLICABLE AT CURBS FOR NON-STRUCTURAL ELEMENTS SUCH AS SKYLIGHTS, INTERIOR PARTITIONS AND INTERIOR RAILINGS
 - SEE ARCH DRAWINGS FOR EMBEDDED PLATES AND BLOCKOUTS. REPLACE REINFORCEMENT INTERRUPTED BY BLOCKOUTS



- NOTES:**
- PLACE CONDUITS BETWEEN TOP AND BOTTOM LAYER OF REINFORCEMENT CENTERED WITHIN SLAB
 - CROSSOVER OF CONDUITS AND/OR PIPES IS NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL BY SER
 - CONDUITS TO BE PLASTIC OR STEEL. USE OF ALUMINUM CONDUITS IS NOT PERMITTED
 - PLACE CONDUITS THE LARGEST OF THE FOLLOWING CLEAR FROM FACE OF COLUMN:
 - LARGEST COLUMN DIMENSION (WIDTH OR DEPTH)
 - 2 X SLAB THICKNESS T
 - 1'-0"
 - MAINTAIN A CLEAR SPACING BETWEEN CONDUITS OF THREE TIMES THE LARGER OUTER DIAMETER OF D1 AND D2, BUT NOT LESS THAN 6 INCHES
 - NO MORE THAN THREE (3) CONDUITS PER SIX (6) FT WIDTH OF SLAB ARE PERMITTED WITHOUT PRIOR WRITTEN APPROVAL BY SER
 - WHERE LARGE NUMBERS OF CONDUIT ENTER THE SLAB AT ONE LOCATION:
 - SUBMIT LAYOUT FOR APPROVAL BY SER
 - FAN OUT CONDUITS IMMEDIATELY
 - PROVIDE ADDITIONAL TOP & BOTTOM REINFORCEMENT AS DIRECTED BY SER UNTIL NOTES 5 AND 6 SPACING REQUIREMENTS ARE MET
 - NO CONDUITS ARE PERMITTED WITHIN A DISTANCE "T" CLEAR FROM SLAB EDGE, SLAB DEPRESSION, OR DROP PANEL WITHOUT PRIOR WRITTEN APPROVAL BY SER
 - WHERE NO BARS ARE PRESENT AT ONE OR MORE FACES OF SLAB, PROVIDE THE FOLLOWING REINFORCEMENT PERPENDICULAR TO THE CONDUIT(S) 3'-0" LONG OR EXTENDING 1'-0" PAST EACH SIDE OF CONDUIT(S), WHICHEVER IS LARGER:
 - T < 8" #4@12" OC
 - 8" < T < 1'-0" #5@12" OC
 - 1'-0" < T < 1'-6" #6@12" OC
 - ANY DEVIATIONS FROM THE ABOVE STATED CONDITIONS REQUIRE PRIOR WRITTEN APPROVAL BY SER

These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesas - 08-23-2019
 DCEE SE-SW Review - Nykia Barnes - 08-23-2019
 DCEE GAR Review - Nykia Barnes - 08-23-2019
 DC Water Review - Vahid Shvardi - 08-23-2019

DCRA APPROVAL STAMP



QUINN EVANS
 ARCHITECTS

2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037


202 298 6700
WWW.QUINNEVANS.COM

**MCMILLAN
 COMMUNITY
 CENTER**

2940 N Capitol St, NW
 Washington, DC
 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00

**TYPICAL
 CONCRETE
 SLAB
 DETAILS**




FOUNDATION TO GRADE
 03/03/17

REVISIONS

NO.	DESCRIPTION	DATE


S4041



1 TYPICAL INTERIOR STAIR DETAIL AT SLAB ON GRADE
 NOT TO SCALE


These plans are conditionally approved as submitted or noted during plan review and are subject to field inspection. Approved plans must be kept on site and are needed for all inspections. No changes or modifications to these plans. Changes require a revision permit with the revised plans. Trade Permits are required for trade work. e.g. Electrical or Plumbing

Plumbing Review - Syed Hashmi - 08-23-2019
 Structural Review - Elton Debesa - 08-23-2019
 DCE SE-SW Review - Nykia Barnes - 08-23-2019
 DCE GAR Review - Nykia Barnes - 08-23-2019
 Water Review - Valhd Silvadi - 08-23-2019




- NOTES:
1. LCN DENOTES LARGER OF ADJACENT CLEAR SPANS
 2. ADDITIONAL MULTI-BAY BOTTOM BARS TO BE SPLICED AS SHOWN ABOVE AND EXTEND 6" INTO SUPPORT AT BAR END

1A TYPICAL TWO-WAY FLAT PLATE - COLUMN STRIP
 NOT TO SCALE



- NOTES:
1. LCN DENOTES LARGER OF ADJACENT CLEAR SPANS
 2. ADDITIONAL MULTI-BAY BOTTOM BARS TO BE SPLICED AS SHOWN ABOVE AND EXTEND 6" INTO SUPPORT AT BAR END

1B TYPICAL TWO-WAY FLAT PLATE - MIDDLE STRIP
 NOT TO SCALE




- NOTES:
1. [Symbol] INDICATES ZONE WHERE OPENINGS ARE NOT PERMITTED WITHOUT WRITTEN APPROVAL BY SER. OPENINGS NOT SHOWN ON STRUCTURAL DRAWINGS MUST BE COORDINATED AND APPROVED BY SER
 2. OPENINGS MEETING THE LIMITATIONS ABOVE SHALL BE PROVIDED WITH REINFORCEMENT AS SHOWN ON PLAN AND FOLLOWING TYPICAL SLAB OPENING DETAILS INCLUDING ADDITIONAL BARS FOR INTERRUPTED REINFORCEMENT
 3. OPENINGS SHALL BE SHOWN ON COORDINATED PENETRATION DRAWINGS AND REINFORCEMENT SHOP DRAWINGS FOR SER REVIEW
 4. OPENINGS NOT MEETING THESE LIMITATIONS MUST BE SUBMITTED TO THE SER FOR COORDINATION, DESIGN, AND APPROVAL PRIOR TO SUBMITTING SHOP DRAWINGS

2 TYPICAL TWO-WAY SLAB OPENING LIMITATIONS
 NOT TO SCALE

- NOTES:
1. SEE PLAN FOR SLAB REINFORCEMENT. BARS SHOWN ABOVE ARE ADDITIONAL TO THOSE SHOWN ON PLAN. BARS SHALL BE LOCATED IN SAME LAYERS AS SLAB REINFORCEMENT. BEAM TOP BARS TO BE LOCATED BELOW SLAB TOP BARS
 2. ADDITIONAL BARS TO BE EQUALLY SPACED WITHIN EXTENT SHOWN ABOVE
 3. ADDITIONAL TOP BARS TO BE HOOKED INTO SUPPORT. ADDITIONAL BOTTOM BARS TO EXTEND 6" INTO SUPPORT

3 TYPICAL BEAM OR WALL SUPPORTED SLAB EXTERIOR CORNER DETAIL
 NOT TO SCALE



DCRA APPROVAL STAMP



2121 WARD PLACE, NW
 4TH FLOOR
 WASHINGTON, DC 20037
 202 298 6700
 WWW.QUINNEVANS.COM


Thornton Tomasetti
 Thornton Tomasetti, Inc.
 2000 L Street, NW, Suite 600
 Washington, DC 20036-4913
 T 202.580.6300 F 202.580.6301

MCMILLAN COMMUNITY CENTER

2940 N Capitol St, NW
 Washington, DC 20002

QEA PROJECT #: 31610100
 TT PROJECT #: M16242.00

TYPICAL CONCRETE TWO-WAY SLAB DETAILS



FOUNDATION TO GRADE
 03/03/17

REVISIONS		
NO.	DESCRIPTION	DATE

S4050



GOVERNMENT OF THE DISTRICT OF COLUMBIA
 Department of Consumer and Regulatory Affairs

All work must be done strictly in accordance herewith an approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be made without approved plans on site. The approval does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections

Statement of Special Inspections

Element	Applicable Code Reference	Y/N	Scope of Service	Agent
Soil		Y		SIER
Excavation	IBC-3304, 1804.1, 1803.5.7 & Construction Docs.	Y		SIER
Earth Retention Systems		N		
Retaining Walls	Plans & Specifications	N		
Sheeting & Shoring w/ or w/o tie backs, post tensioning or Rock Anchors	Plans & Specifications	N		
Soil Nailing Systems	Plans & Specifications	N		
Drilled piers	Plans & Specifications	N		
Sheet piling	Plans & Specifications	N		
Tied-back walls	Plans & Specifications	N		
Slurry walls	Plans & Specifications	N		
Fill Placement	IBC-1705.6, Table 1705.6 (3,4,5)	Y		SIER
Shallow Foundations	IBC-Table 1705.6 (1,2)	N		
Deep Foundations	IBC-1803.5.5, 1803.5.6	Y		SIER
Driven deep foundations	IBC-1705.7, Table 1705.7	N		
Cast-in-place deep foundations	IBC-1705.8, Table 1705.8, IBC-1705.3	Y		SIER

Element	Applicable Code Reference	Y/N	Scope of Service	Agent
Specialty piles to include Micro piles, herical piers, geo- piers or other similar Systems	IBC-1705.9, 1810.4.10, 1810.4.11, and const. documents by RDPRC	N		Permit # FD1800040 Date 08/23/19 All work must be done strictly in accordance herewith an approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be made without approved plans on site. The approval does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections
Cast-in-place concrete	IBC-1705.3, Table 1705.3	Y		SIER
Sampling of fresh concrete, fabricate specimen for strength test, perform slump and air content test, and to determine the temperature of the concrete	T1705.3 (6), ASTM C-172, ASTM C-31, ACI 318:5.6, 5.8	Y		SIER
Verification of required mix design	IBC-1904.2, 1910.2, 1910.3, ACI 318: CH 4,5.2-5.4	Y		SIER
Reinforcing steel welding	IBC-T-1705.2.2 (2b), AWS D1.4, ACI 318:3.5.2	Y		SIER
Bolts, inserts & anchors	IBC-T-1705.3 (3), 1908.5 & 1909.1, ACI 318:8.1.3, 21.2.8	Y		SIER
Anchors post installed in hardened concrete	T-1705.3 (4), 1909.1, ACI 318:3.8.6, 8.1.3, 21.2.8	Y		SIER
Formwork shoring & reshoring	T-1705.3 (12)	Y		SIER
Formwork stripping & reshoring	T-1705.3(11), ACI 318, Section 6.2	Y		SIER
Inspection for maintenance of specified curing temperature & techniques	T-1705.3 (8), IBC Sec 1910.9, ACI 318: 5.11-5.13	Y		SIER
Verification of concrete strength prior to stressing the tendons in post tension concrete and prior to stripping the form work	T-1705.3 (11), ACI 318:6.2	Y		SIER
Structural Steel	IBC-1705.2.1, AISC 360	Y		SIER
Inspection of fabricators	IBC-1704.2.5	Y		SIER

Element	Applicable Code Reference	Y/N	Scope of Service	Agent
Special Inspections for Seismic Resistance	IBC-1705.11	N		Permit # FD1800040 Date 08/23/19 All work must be done strictly in accordance herewith an approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be made without approved plans on site. The approval does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections
Structural Steel	IBC-1705.11.1, AISC 341	N		
Cold-formed steel lihgt-frame construction	IBC-1705.11.3	N		
Special Inspections for wind resistance	IBC-1705.10	N		
Material verification of cold-formed steel deck	T-1705.2.2 (1) a,b and Applicable ASTM standards	N		
Inspection of Welding	T-1705.2.2(2)	N		
Cold-formed steel deck	T-1705.2.2.a(1), AWS D1.3	N		
Reinforcing steel other than ASTM, A706	T-1705.2.2 (2) b (1)	N		
Reinforcing steel resisting axial, flexural forces in intermediate & special frames	T-1705.2.2 (2) b (2), AWS D1.4, ACI 318: Sec 3.5.2	N		
Shear reinforcement	T-1705.2.2 (2) b (3), AWS D1.4, ACI 318: Section 3.5.2	N		
Other reinforcing steel	T-1705.2.2 (2) b (4), AWS D1.4, ACI 318: Section 3.5.2	N		
Erection cold-formed steel trusses spanning 60 feet or greater	IBC-1705.2.2.2	N		
Precast Concrete		N		
Inspection of fabricators	IBC-1704.2.5	N		
Erection of precast concrete members handling, bracing, inspection of welded connections	T-1705.3 (10), ACI 318: CH. 16	N		

Element	Applicable Code Reference	Y/N	Scope of Service	Agent
Inspection of bolts, inserts, & anchors	IBC-1908.5, 1909.1, T-1705.3 (3), ACI 318:8.1.3, 21.2.8	N		Permit # FD1800040 Date 08/23/19 All work must be done strictly in accordance herewith an approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be made without approved plans on site. The approval does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections
Masonry	IBC-1705.4	N		
Constructing & Testing Masonry Prisms	ASTM C-1314	N		
Mortar & Grout Proportions	ASTM C-270, ASTM C-476	N		
Sampling & Testing Masonry Grout	ASTM 1019-14	N		
Hot Weather Protection	ACI 530.1-98/ ASCE 6-98/ TMS 602-98	N		
Cold Weather Protection	ACI 530.1-98/ ASCE 5-98/TMS 402-98	N		
Placement of Reinforcement	National Concrete Masonry Association: TEK 12-4C	N		
Emp.- Cat. IV, Engr.- Cat. I, II, III- Level B Quality Assurance of Building Code requirements and specifications for masonry structures.	TMS 402-11/ ACI 530-11/ ASCE 5-11	N		
Engr. - Cat. IV Level- C Quality Assurance of Building Code requirements and specifications for masonry structures.	TMS 402-11/ ACI 530-11/ ASCE 5-11	N		
Wood	IBC-1705.5	N		
Inspection of fabricators	IBC-1704.2.5	N		
High-load diaphragms	IBC-1705.5.1	N		
Seismic- resistance Systems	IBC-1705.11.2	N		
Wind resistance systems	IBC-1705.10.1	N		

Element	Applicable Code Reference	Y/N	Scope of Service	Agent
Metal-plate-connected wood trusses spanning 60 feet or greater	IBC-1705.5.2	N		Permit # FD1800040 Date 08/23/19 All work must be done strictly in accordance herewith an approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be made without approved plans on site. The approval does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections
Sprayed Fire- resistant materials	IBC-1705.13			
Thickness, density, bond strength test	IBC-1705.13.4, 1705.13.5, 1705.13.6			
Mastic & intumescent resistant coating	IBC-1705.14			
Exterior insulation & finish Systems(EIFS)	IBC-1705.15			
Fire-resistant penetrations & joints	IBC-1705.16			
Penetration fire stops	IBC-1705.16.1			
Fire-resistant joint systems	IBC-1705.16.2			
Smoke Control Systems	IBC-1705.17			
Mechanical-Electrical Supports, Seismic-resisting Systems	IBC-1705.11.6			
Tower Cranes	Chapter 13 of Special Inspections Manual	Y		SIER

*RDPRC- Registered Design Professional in Responsible Charge

**GOVERNMENT OF THE DISTRICT OF COLUMBIA
DEPARTMENT of CONSUMER AND REGULATORY AFFAIRS**



Inspection and Compliance Administration
Third Party Specialty & Inspections Program

All work must be done strictly in accordance with approved plans. Approved plans shall be kept on the site until completion of the construction. No inspection will be performed without approved plans on site. The permit does not prevent a field inspection from ordering corrections to meet codes when issues are noted during inspections.

Statement of Special Inspections

Project: McMillan Community Center

Permit: FD18000040 **Construction Type:** McMillan Community Center

Address: 2940 N. Capitol St., NW, Washington, DC 20002 **Group:** _____

Project Description: 2 Story Community Center w/ Pool on Lower Level & Multipurpose Room on Upper Level **Problem** _____ **Prepared** _____
Soil (Y/N): _____ **Fill (Y/N):** _____
Height _____ **Total** _____ **Sprinkler** _____ **Fire Alarm** _____ **Occupancy** _____ **Seismic** _____
Stories: 2 **Area ft.** 18,955 **sf (Y/N):** Y **(Y/N):** Y **Category:** B, A-3, Desn. Cat: S-2 & H

Building owner DC Department of General Services
 Name _____ Company _____

Owner address 1250 U Street, NW Washington, DC 20009
 Street Address _____ City _____ State _____ Zip _____

Architect of Record Larry Barr, FAIA ARC 100516 Quinn Evans Architects
 Name _____ License No. _____ Company _____

Structural Engineer of Record Mark Tamaro, P.E. 900640 Thornton Tomasetti, Inc.
 Name _____ License No. _____ Company _____

General Contractor Tony Barton 70107331 Gilbane Building Company
 Name _____ License No. _____ Company _____

Special inspections Engineer of record _____
 Name _____ License No. _____ Company _____

Inspection and testing agency _____
 Company _____

This Statement of Special Inspections is submitted in accordance with Section 1704.2.3 of the 2012 International Building Code. It includes a Schedule of Special Inspection Services Applicable to the above-referenced projects as well as the identity of the individuals, agencies, or firms' intended for conducting these inspections. The Special Inspector(s) shall keep records of all specified special inspections and shall furnish interim special inspection reports to the Building Official and to the Registered Design Professional in Responsible Charge prior to completion of that phase of work. A final report of Special Inspections documenting required Special Inspection and corrections of any discrepancies noted in the special inspection reports shall be submitted to the Building Official and the Registered Design Professional in Responsible Charge at the conclusion of the project.

The Special Inspection program does not relieve the Contractor of the responsibility to comply with the Contract Documents. Jobsite safety and means and methods of construction are solely the responsibility of the Contractor.

Statement of Special Inspections
Prepared By: Mark Tamaro, P.E. **Signature/Date:**  4-17-19

Reviewed By: Registered Design Professional **Signature/Date:**  4-17-19

Building Owner's Authorization **Signature/Date:** _____

Building official's Acceptance **Signature/Date:** _____