



SOIL EROSION & SEDIMENT CONTROL NOTES

1. ALL SEDIMENT AND EROSION CONTROL METHODS SHALL BE INSTALLED BEFORE THE START OF ANY EXCAVATION AND / OR CONSTRUCTION AS PER STANDARDS AND SPECIFICATIONS FOR SOIL EROSION FOR WASHINGTON, DC. CONTACT 202-535-2937 FOR AN ON SITE INSPECTION PRIOR TO ANY LAND DISTURBING ACTIVITY. IF AN ON-SITE INSPECTION REVEALS FURTHER EROSION CONTROL MEASURES ARE NECESSARY, THE SAME SHALL BE PROVIDED.
2. ALL DEBRIS IS TO BE REMOVED FROM THE SITE.
3. ALLEY AND / OR STREET SHALL BE SWEEP CLEAN AT ALL TIMES DURING EXCAVATION AND CONSTRUCTION.
4. ALL SEDIMENT AND EROSION CONTROL MEASURES TO BE INSPECTED DAILY BY THE CONTRACTOR. ANY DAMAGED DEVICE OR MEASURE WILL BE REPAIRED OR REPLACED BY THE CLOSE OF BUSINESS OR AS SUGGESTED BY THE ARCHITECT.
5. ALL VEHICLES LEAVING THE SITE SHALL EXIT THROUGH THE CONSTRUCTION ENTRANCE ONLY AND SHALL BE WASHED DOWN TO REMOVE MUD FROM TIRES BEFORE ENTERING THE STREET. CONSTRUCTION ENTRANCE TO BE MAINTAINED IN GOOD WORKING CONDITION.
6. ALL CATCH BASINS AND AREA DRAINS SHALL BE PROTECTED DURING EXCAVATION AND CONSTRUCTION.
7. IF A CATCH BASIN OR DRAIN BECOMES CLOGGED AS A RESULT OF EXCAVATION OR CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS IMMEDIATE CLEANING.
8. ALL DISTURBED AREAS WITHIN THE LIMIT OF DISTURBANCE BOUNDARY NOT SHOWN TO BE PAVED SHALL BE SEEDED OR SODDED PER WASHINGTON, DC SPECIFICATIONS WITHIN SEVEN DAYS OF DISTURBANCE.
9. ANY STOCKPILING, REGARDLESS OF LOCATION ON SITE, SHALL BE STABILIZED WITH PLASTIC OR CANVAS, AFTER ITS ESTABLISHMENT AND FOR THE DURATION OF THE PROJECT.
10. AFTER RATE OF DEMOLITION, THE CONTRACTOR SHALL PROVIDE GROUND COVER TO PREVENT EROSION AND SEDIMENT RUN-OFF FROM OCCURRING, SUCH AS STRIP SOIL, PAVING, BRICK/BRACK, OR MULCH, ETC.
11. AT THE COMPLETION OF CONSTRUCTION AND AFTER THE WASHINGTON, DC. EROSION AND SEDIMENT CONTROL INSPECTOR APPROVAL, ALL TEMPORARY SITUATION, SEDIMENTATION AND EROSION CONTROL MEASURES AND DEVICES SHALL BE REMOVED AND ALL DE-NUDED AREAS SHALL BE PERMANENTLY STABILIZED.
12. CONTRACTOR TO INSTALL INLET PROTECTION AT THE NEAREST DOWNSTREAM STORM INLET PRIOR TO LAND DISTURBING ACTIVITY - SEE DETAILS PAGE C-008.

SOIL EROSION & SEDIMENT CONTROL NARRATIVE
ALL EXCAVATION WORK TO BE PERFORMED IS LOCATED WITHIN THE FOOTPRINT OF THE EXISTING PROPERTY IN ORDER TO CREATE NEW FOOTINGS FOR NEW SCREEN-IN PORCH, AS WELL AS NEW GRAVEL PIT FOR STORM WATER MANAGEMENT.
ESC STEP BY STEP: - SAWCUT AND REMOVE CONCRETE AT FOOTING AND GRAVEL PIT LOCATIONS. - EXCAVATE FOOTINGS AND GRAVEL PIT; PLACE EXCAVATED SOIL DIRECTLY INTO TRUCK OR COVERED CONTAINER. - INSTALL GRAVEL PIT, FORM AND POUR FOOTINGS. - BACKFILL AND RESTORE CONCRETE SLAB. - REMOVE TEMPORARY ESC MEASURES AFTER FINAL STABILIZATION AND DOEE APPROVAL.

aggregate
architecture+design
1012 14th St NW Suite 915, Washington, DC 20005 | (202) 789-0353
Aggregate Architecture & Design, PLLC © 2008