ARNOLD & PORTER

202.942.5000
202.942.5999 Fax

555 Twelfth Street, NW
Washington, DC 20004-1206

April 15, 2002

RECEIVED
D.C. OFFICE OF ZONING
2002 APR 16 AM 7:26

Carol Mitten, Chair
D.C. Zoning Commission
441 4th Street, N.W.
Suite 210
Washington, D.C. 20001

Re: Zoning Commission Case No. 01-36C (Unified Communications Center)

Dear Ms. Mitten and Members of the Commission:

We are writing on behalf of the Applicant in this case, the Office of the Chief Technology Officer of the District of Columbia ("OCTO"), in response to respond to letters from Advisory Neighborhood Commissions ("ANCs") 8A (in which the subject property is located) and 8C. Both letters request a postponement of the hearing for the same two reasons: i. alleged health issues surrounding the presence of fly ash on the subject property and ii. inadequate consultations with the ANCs. The purpose of this letter is to assure the Zoning Commission, based on facts presented herein, that there is no need to postpone the public hearing. Consultations with a wide range of community groups in Ward 8, including the ANCs, has taken place over a period of months. Also, OCTO has responsibly and in a technically skilled way dealt with the issue of fly ash.

Fly Ash. In developing the plans for the Unified Communications Center ("UCC"), OCTO and its consultants have obtained expert findings, and they offer a complete program regarding the fly ash, as summarized below:

- In addition to the expert study performed on behalf of WMATA in 1995 (which found the material to be inert and safe), OCTO has a more recent report by the URS Corporation. The latter report tested the fly ash and found it to be non-hazardous and below the U.S. EPA Risk Based Concentration ("RBC") for commercial soil. A copy of the URS report is enclosed for the record of this PUD case.
- The architects sited the UCC building so as to avoid the area with fly ash deposits, which would be an unstable foundation and would be significantly disturbed by excavation for building foundation.
- The surface parking area will cover most of the fly ash area and effectively seal it. OCTO believes this is actually a mitigation measure, in that covering the ash with asphalt provides a sealing process, whereas the fly ash is currently compacted and exposed to the elements.

ZONING COMMISSION
District of Columbia
Case 01-36C
Exhibit 26

ZONING COMMISSION
District of Columbia
CASE NO.01-36C
EXHIBIT NO.26

- OCTO is following all applicable laws and regulations in this regard. We have successfully completed the Environmental Screening Process of the Department of Consumer and Regulatory Affairs, which was quite rigorous. And, in handling the fly ash OCTO will follow applicable federal and local laws and procedures.
- In national as well as local terms, this is far from a unique environmental condition, and the applicable laws and regulations fully control the situation.
- The issue of the fly ash is also addressed on pages 24-25 of the Pre-Hearing Submission, dated and submitted to the record on February 8, 2002.

In short, there is ample technical and expert information about the issue for the zoning hearing to proceed as scheduled, and the responsible government agencies are doing their jobs within a full complement of environmental laws and regulations.

Community Involvement and Outreach. On pages 17-18 of our Pre-Hearing Statement dated February 8 of this year, we list 19 community organizations that OCTO had met with as of that date. Numerous additional consultations with individuals and groups, including ANC Commissioners and ANCs at meetings, have occurred since that time. These consultations have included responses and adjustments to issues raised, including the fly ash. Attached to this letter is the cover page and one of several response sheets from OCTO's Power Point presentation dated November 29, 2001, which was used in community meetings. As you can see, on this page OCTO informed the community about its environmental processing status and its response regarding fly ash. The fly ash and other issues have been discussed with many community groups in Ward 8, as well as with the applicable government agencies.

For the reasons set forth above, the Office of the Chief Technology Officer, the Applicant in this case, requests that the Zoning Commission not postpone the public hearing. This is a high priority project of the District of Columbia that needs to proceed expeditiously. Thank you for your consideration.

Sincerely,

Nathan W. Gross, AICP

Cynthia A. Giordano

Cc: Advisory Neighborhood Commission 8A
Advisory Neighborhood Commission 8C

04/15/02 18:51 FAX 202 842 5999 A & P FAX CTR DC #9 004

UNIFIED COMMUNICATIONS CENTER
DISTRICT OF COLUMBIA

Unified Communication Center
An Opportunity

Economic Development and Benefits for Ward 8

November 29, 2001

04/15/02 18:51 FAX 202 942 5999 A & P FAX CTR DC #9 005

What We Heard – **Campus Environment**

- **Concern:** Environmental Impacts

- **Action:** Completed the Environmental Impact Screening process. Results submitted to DCRA, DOH, WASA, and DPW/DDOT.
- No significant environmental impacts have been identified.
- The fly ash was tested and confirmed to be an inert material. The UCC project will take the added step of building around the fly ash. UCC-related traffic will be a modest addition to the existing St. Elizabeths traffic (no additional traffic light required).



RECEIVED
JAN 2 4 2002
DISTRIBUTED

URS

January 10, 2002

Mr. Dave Talley
Jacobs Facilities, Inc.
1111 19th Street, NW
Washington, DC 20036

Subject: **Final Report**
Sampling and Chemical Analysis Results – Ash Fill Area
Proposed Parking Lot for Unified Communications Center
Washington, D.C.
Subcontract Number F5-257422-S-01-0001

Dear Mr. Talley:

URS Group, Inc. (URS) is pleased to present to Jacobs Facilities, Inc. (Jacobs) the results of the analyses of soil/ash samples collected in the ash fill area of the proposed parking lot for the Unified Communications Center (UCC) on the campus of St. Elizabeths Hospital in Washington, D.C. It is URS's understanding that some of the existing fill material at the site may be excavated in order to construct the proposed UCC. Therefore, the purpose of this work is to characterize the ash fill material in the vicinity of the project for disposal and identify constituents present in the ash fill material. In order to characterize the fill material, URS collected two field samples of the ash fill material for laboratory analysis.

Previous reports indicate that the fill area on the subject property consists of non-hazardous incinerator ash from the Benning Road incinerator, placed on site from 1977 to 1989. Boring data indicates the fill area is up to 39 feet thick. The ash placement was authorized under two Revocable Licenses for Real Property (October 1977 and October 1982) issued to the District of Columbia Government, Department of Environmental Services by the United States of America, represented by St. Elizabeths Hospital, National Institute of Mental Health, Public Health Service, Department of Health, Education and Welfare. The licenses authorized the disposal of incinerator ash to be supplemented with dirt. Paper, trash, concrete and wood were not allowed to be disposed on site; however, boring data indicates some of these materials have been disposed along with the ash. According to previous reports, a site investigation conducted by EPA in 1991 found no immediate risks to human health or the environment and identified the site as having a low priority for cleanup.

FIELD ACTIVITIES AND SAMPLE COLLECTION

In accordance with the Scope of Work (SOW) dated November 30, 2001, a Jacobs Project Manager, Don Eischens, identified six sampling locations within the proposed UCC excavation area. URS marked these sampling locations and designated them Sample Location 1 through 6 (see Figure 1). URS utilized a hand auger to reach the sample depths shown in Figure 1. The

URS Corporation
200 Orchard Ridge Drive, Suite 101
Gaithersburg, MD 20878

URS

samples were collected at depths where the soil appeared to contain ash. Surface aggregate and densely packed fill material prevented hand auger advancement to the proposed collection depth of 12" – 18" at Sample Locations 1, 2, 3, 5, and 6. Samples collected from Sample Locations 1, 2, 3, 5, and 6 were combined to form a composite sample. The composite sample was analyzed for hazardous waste characteristics of toxicity by metals and organic compounds under the Resource Conservation and Recovery Act (RCRA). RCRA characteristics were investigated to characterize the fill material for disposal. One discrete sample was collected at Sample Location 5 and split into two jars. The discrete sample was analyzed for semi-volatile organic compounds (SVOCs) and 13 priority pollutant metals. Sample Location 4 was advanced to a depth of 16" and only trace amounts of ash were identified, therefore no sample was collected from Sample Location 4.

In order to limit cross-contamination, equipment used for sample collection was washed in an Alconox (biodegradable cleaner) and distilled water solution and rinsed with distilled water between sample locations. After collecting the samples, URS placed the samples with ice and they were picked up by Phase Separation Science, Inc. (PSS), an analytical laboratory subcontracted to URS. The samples were handled using industry standard chain of custody procedures.

LABORATORY ANALYSIS RESULTS

PSS conducted the analysis for the 13 priority pollutant metals on December 12, 2001, seven metals were detected. The analysis for SVOCs was performed on December 11, 2001, one SVOC was detected. The RCRA characteristics analysis was performed on December 12, 13 and 14, 2001. All RCRA characteristic parameters were below detection limits. The results of the soil sample laboratory analyses are included in Appendix A.

CONCLUSIONS

Based on the analyses collected, the following conclusions regarding the ash waste within the Jacobs defined limits have been reached:

- The ash waste when removed and disposed would not be classified as a RCRA hazardous waste for metals, pesticides/herbicides, volatile organic compounds, or semivolatile organic compounds.

- Of the constituents (seven metals and one SVOC) detected in the discrete grab sample from Sample Location 5, only the concentration of Arsenic exceeds the US EPA Region Risk-Based Concentration (RBC) Screening Level for residential soil (currently 0.43 mg/kg). However, the level detected does not exceed the RBC for commercial soil, currently 3.8 mg/kg.

URS

Mr. Dave Talley
Jacobs Facilities, Inc.
Page 3

LIMITATIONS

This site investigation was intended to characterize the incinerator ash fill material located on St. Elizabeths campus in the area of the proposed Unified Communications Center The investigation can only identify contamination to the extent that it was known or suspected through observation or usage on the subject site. The attached analytical results only represent the characteristics of the soil/ash at the locations sampled and are not necessarily representative of the soil/ash at other locations on the subject site. It is possible that the disposal facility will require additional waste characterization testing at the time of disposal.

There is no investigation thorough enough to preclude the presence of materials on the subject site that presently, or in the future, may be considered hazardous. Because regulatory evaluation criteria are constantly changing, concentrations of contaminants present and considered to be acceptable may, in the future, become subject to different regulatory standards and require remediation.

Opinions and judgement expressed herein, which are based on our understanding and interpretation of current regulatory standards, should not be construed as legal opinions. Even the most comprehensive sampling and testing program, using the best available techniques, may derive inferences from samples that are not truly representative.

This report has been prepared solely for the use of Jacobs Facilities and the UCC project. No third party shall have the right to rely on URS opinions rendered in connection with the services or in this document without URS's written consent and the third party's agreement to be bound to the same conditions and limitations as Jacobs.

If you have any questions regarding the content of this letter, or if you require additional information, please do not hesitate to contact Chuck Georgius at (301) 670-3333.


Very truly yours,

URS Corporation

Charles R. Georgius Jr.

Charles R. Georgius, Jr., CHMM
Project Manager

Attachments: Figure 1 – Sketch of Current Site Conditions and Sample Locations
Appendix A Laboratory Analysis Results



LEGEND

- BUILDING
- TREES
- PIEZOMETER
- DRY TRANSFORMER
- PROJECT SITE BOUNDARY
- LIMIT OF FILL PLACEMENT

0 75' 150'

SCALE IN FEET

SOURCE: KIMBALL AND ASSOCIATES, MARCH 19, 2001

CLIENT	JACOBS FACILITIES		
PROJ	Proposed UCC, St. Elizabeths Hospital, Washington DC		
REVISION NO		DES BY	
SCALE	AS SHOWN	DR BY	
FILE		CHK BY	

TITLE: Soil/Ash Sample Locations (and sample depth)

URS

PROJ NO 60-72001010

FIGURE 1

04/15/02 18:52 FAX 202 942 5999 A & P FAX CTR DC #9 009

OFFICES:
6630 BALTIMORE NATIONAL PIKE
ROUTE 40 WEST
BALTIMORE, MARYLAND 21228
410-747-8770
800-932-9047
410-788-8723 Fax
www.phaseonline.com

PHASE SEPARATION SCIENCE, INC.

ANALYTICAL CHEMISTRY • ENVIRONMENTAL SCIENCE

CERTIFICATE OF ANALYSIS
No. 01120718-01 Page 1 of 3
URS Corporation - Gaithersburg
December 14, 2001

Project: UCC-Jacobs Facilities
Site Location: S.E., Washington, D.C.
Project Number: 89-F2001016.00
Matrix: Soil

Date Sampled: 12/07/01
Date Received: 12/07/01

Sample ID: Sample Location 5		Result	Unit	Method	PQL	Prepared	Analyzed
Priority Pollutant Metals							
Antimony	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Arsenic		1.4	mg/kg	EPA 200.8	0.5	12/10/01	12/12/01
Beryllium	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Cadmium	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Chromium		16	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Copper		24	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Lead		28	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Mercury		0.2	mg/kg	EPA 200.8	0.1	12/10/01	12/14/01
Nickel		54	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Selenium	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Silver	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Thallium	<	2.5	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Zinc		22	mg/kg	EPA 200.8	2.5	12/10/01	12/12/01
Semi-Volatile Organic Compounds							
Acenaphthene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Acenaphthylene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Anthracene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzo (a) anthracene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzo (b) fluoranthene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzo (k) fluoranthene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzoic acid	<	24750	ug/kg	EPA 8270	24750	12/11/01	12/11/01
Benzo (g,h,i) perylene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzo (a) pyrene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Benzyl alcohol	<	9900	ug/kg	EPA 8270	9900	12/11/01	12/11/01
Bis (2-chloroethoxy) methane	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Bis (2-chloroethyl) ether	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Bis (2-chloroisopropyl) ether	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Bis (2-ethylhexyl) phthalate	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-bromophenyl phenyl ether	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Butyl benzyl phthalate	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-Chloroaniline	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-Chloro-3-methylphenol	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Chloronaphthalene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Chlorophenol	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-Chlorophenyl phenyl ether	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Chrysene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01

OFFICES:
6630 BALTIMORE NATIONAL PIKE
ROUTE 40 WEST
BALTIMORE, MARYLAND 21228
410-747-8770
800-932-9047
410-788-8723 Fax
www.phaseonline.com

PHASE SEPARATION SCIENCE, INC.

ANALYTICAL CHEMISTRY • ENVIRONMENTAL SCIENCE

CERTIFICATE OF ANALYSIS
No. 01120718-01 Page 2 of 3
URS Corporation - Gaithersburg
December 14, 2001

Project: UCC-Jacobs Facilities
Site Location: S.E., Washington, D.C.
Project Number: 89-F2001016.00
Matrix: Soil

Date Sampled: 12/07/01
Date Received: 12/07/01

Sample ID: [redacted]	Result	Unit	Method	PQL	Prepared	Analyzed
Semi-Volatile Organic Compounds						
Di-n-butyl phthalate	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Dibenzofuran	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
1,2-Dichlorobenzene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
1,3-Dichlorobenzene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
1,4-Dichlorobenzene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
3,3-Dichlorobenzidine	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2,4-Dichlorophenol	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
Diethyl phthalate	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2,4-Dimethylphenol	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Dimethyl phthalate	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4,6-Dinitro-2-methylphenol	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
2,4-Dinitrophenol	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2,4-Dinitrotoluene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2,6-Dinitrotoluene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Di-n-octyl phthalate	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Fluoranthene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Fluorene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Hexachlorobenzene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Hexachlorobutadiene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Hexachlorocyclopentadiene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Hexachloroethane	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Indeno (1,2,3-cd) pyrene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Isophorone	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Methylnaphthalene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Methylphenol	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-Methylphenol	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Naphthalene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Nitroaniline	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
3-Nitroaniline	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
Nitrobenzene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2-Nitrophenol	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
4-Nitrophenol	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
N-Nitrosodiphenylamine	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
N-Nitroso-di-n-propylamine	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
Pentachlorophenol	< 12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
Phenanthrene	< 4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01

OFFICES:
6630 BALTIMORE NATIONAL PIKE
ROUTE 40 WEST
BALTIMORE, MARYLAND 21228
410-747-8770
800-932-9047
410-788-8723 Fax
www.phaseonline.com

PHASE SEPARATION SCIENCE, INC.

ANALYTICAL CHEMISTRY • ENVIRONMENTAL SCIENCE

CERTIFICATE OF ANALYSIS
No. 01120718-01 Page 3 of 3
URS Corporation - Gaithersburg
December 14, 2001

Project: UCC-Jacobs Facilities
Site Location: S.E., Washington, D.C.
Project Number: 89-F2001016.00
Matrix: Soil

Date Sampled: 12/07/01
Date Received: 12/07/01

Sample ID: [redacted]		Result	Unit	Method	PQL	Prepared	Analyzed
Semi-Volatile Organic Compounds							
Pyrene	e	870	ug/kg	EPA 8270	4950	12/11/01	12/11/01
1,2,4-Trichlorobenzene	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01
2,4,5-Trichlorophenol	<	12450	ug/kg	EPA 8270	12450	12/11/01	12/11/01
2,4,6-Trichlorophenol	<	4950	ug/kg	EPA 8270	4950	12/11/01	12/11/01

Notes/Comments:
PQL - Practical Quantitation Limit
Results reported on an as received basis
e - estimated value, less than quantitation limit

Reviewed By: Matt Cohen
Quality Assurance Chemist

OFFICES:
6630 BALTIMORE NATIONAL PIKE
ROUTE 40 WEST
BALTIMORE, MARYLAND 21228
410-747-8770
800-932-9047
410-788-8723 Fax
www.phaseonline.com

PHASE SEPARATION SCIENCE, INC.

ANALYTICAL CHEMISTRY • ENVIRONMENTAL SCIENCE

CERTIFICATE OF ANALYSIS
No. 01120718-02 Page 1 of 2
URS Corporation - Gaithersburg
December 14, 2001

Project: UCC-Jacobs Facilities
Site Location: S.E., Washington, D.C.
Project Number: 89-F2001016.00
Matrix: Soil

Date Sampled: 12/07/01
Date Received: 12/07/01

Sample ID: [redacted]	Result	Unit	Method	Limits	Extracted	Analyzed
TCLP Metals						
Arsenic	< 0.5	mg/L	1311/200.8	5	12/10/01	12/12/01
Barium	< 10	mg/L	1311/200.8	100	12/10/01	12/12/01
Cadmium	< 0.1	mg/L	1311/200.8	1	12/10/01	12/12/01
Chromium	< 0.5	mg/L	1311/200.8	5	12/10/01	12/12/01
Lead	< 0.5	mg/L	1311/200.8	5	12/10/01	12/12/01
Mercury	< 0.1	mg/L	1311/200.8	0.2	12/10/01	12/14/01
Selenium	< 0.1	mg/L	1311/200.8	1	12/10/01	12/12/01
Silver	< 0.5	mg/L	1311/200.8	5	12/10/01	12/12/01
TCLP Herbicides						
2,4,5-TP(Silvex)	< 100	ug/L	1311/8151	1000	12/10/01	12/14/01
2,4-D	< 100	ug/L	1311/8151	10000	12/10/01	12/14/01
TCLP Pesticides						
Lindane	< 5	ug/L	1311/8081	400	12/10/01	12/13/01
Heptachlor	< 5	ug/L	1311/8081	8	12/10/01	12/13/01
Heptachlor Epoxide	< 5	ug/L	1311/8081	8	12/10/01	12/13/01
Endrin	< 5	ug/L	1311/8081	20	12/10/01	12/13/01
Methoxychlor	< 5	ug/L	1311/8081	10000	12/10/01	12/13/01
Toxaphene	< 25	ug/L	1311/8081	500	12/10/01	12/13/01
Chlordane	< 25	ug/L	1311/8081	30	12/10/01	12/13/01
TCLP Semi-Volatiles						
o-Cresol	< 20	ug/L	1311/8270	200000	12/10/01	12/12/01
p-Cresol	< 20	ug/L	1311/8270	200000	12/10/01	12/12/01
m-Cresol	< 20	ug/L	1311/8270	200000	12/10/01	12/12/01
2,4-Dinitrotoluene	< 20	ug/L	1311/8270	130	12/10/01	12/12/01
Hexachloroethane	< 20	ug/L	1311/8270	3000	12/10/01	12/12/01
Hexachlorobenzene	< 20	ug/L	1311/8270	130	12/10/01	12/12/01
Nitrobenzene	< 20	ug/L	1311/8270	2000	12/10/01	12/12/01
Pentachlorophenol	< 100	ug/L	1311/8270	100000	12/10/01	12/12/01
Pyridine	< 20	ug/L	1311/8270	5000	12/10/01	12/12/01
	< 20	ug/L	1311/8270	400000	12/10/01	12/12/01

OFFICES:
6630 BALTIMORE NATIONAL PIKE
ROUTE 40 WEST
BALTIMORE, MARYLAND 21228
410-747-8770
800-932-9047
410-788-8723 Fax
www.phaseonline.com

PHASE SEPARATION SCIENCE, INC.

ANALYTICAL CHEMISTRY • ENVIRONMENTAL SCIENCE

CERTIFICATE OF ANALYSIS
No. 01120718-02 Page 2 of 2
URS Corporation - Gaithersburg
December 14, 2001

Project: UCC-Jacobs Facilities
Site Location: S.E., Washington, D.C.
Project Number: 89-F2001016.00
Matrix: Soil

Date Sampled: 12/07/01
Date Received: 12/07/01

Sample ID: [illegible]	Result	Unit	Method	Limits	Extracted	Analyzed
TCLP Volatiles						
Benzene	< 100	ug/L	1311/8260	500	12/10/01	12/12/01
Carbon Tetrachloride	< 100	ug/L	1311/8260	500	12/10/01	12/12/01
Chloroform	< 100	ug/L	1311/8260	6000	12/10/01	12/12/01
1,2-Dichloroethane	< 100	ug/L	1311/8260	500	12/10/01	12/12/01
Tetrachloroethene	< 100	ug/L	1311/8260	700	12/10/01	12/12/01
Vinyl Chloride	< 100	ug/L	1311/8260	200	12/10/01	12/12/01
2-Butanone	< 200	ug/L	1311/8260	200000	12/10/01	12/12/01
Chlorobenzene	< 100	ug/L	1311/8260	100000	12/10/01	12/12/01
1,4-Dichlorobenzene	< 100	ug/L	1311/8260	7500	12/10/01	12/12/01
1,1-Dichloroethene	< 100	ug/L	1311/8260	700	12/10/01	12/12/01
Trichloroethene	< 100	ug/L	1311/8260	500	12/10/01	12/12/01

Notes/Comments:
Results reported on an as received basis

Reviewed By: Matt Cohee
Quality Assurance Chemist

ARNOLD & PORTER

202.942.5000
202.942.5999 Fax

555 Twelfth Street, NW
Washington, DC 20004-1206

D.C. OFFICE OF ZONING
2002 APR 16 AM 7:26

Fax Transmittal

Date: 4/15/02

RECIPIENT NAME(S)	RECIPIENT FAX NUMBER(S)	RECIPIENT TELEPHONE NUMBER(S)	RECIPIENT ROOM #(S)
Office of Zoning Attn: Alberto Bastida	202-727-6072	727-6311	

SENDER	SENDER'S TELEPHONE NUMBER	SENDER'S ROOM NUMBER
Nate Gross	202-942-5956	1230A

CLIENT/MATTER NUMBER	TIMEKEEPER NUMBER	TOTAL NUMBER OF PAGE(S)
17940.002	NG7256	We are transmitting 13 page(s) (including this cover sheet)

TRANSMISSION DEADLINE (DATE & TIME)	ALTERNATE TELEPHONE NUMBER (OPTIONAL)
This document must be transmitted no later than: ASAP	Alternate telephone number at which the sender can be reached if there are difficulties with this fax:

If you experience difficulty receiving this fax transmission, please contact the operator at 202.942.5837.

MESSAGE

PRIVILEGED AND CONFIDENTIAL

Information intended only for the use of the addressee named above. If the reader of this message is not the intended recipient or the employee or agent responsible for delivering the message to the intended recipient, please note that any dissemination, distribution or copying of this communication is strictly prohibited. Anyone who receives this communication in error should notify us immediately by telephone and return the original message to us at the above address via the U.S. Mail.