ESTIMATED QUANTITIES OF POTABLE WATER, SANITARY SEWAGE AND STORM WATER GENERATED BY PROJECT

ESTIMATED QUANTITY OF POTABLE WATER:

Mansion Building - 35 GPM (gallons per minute)*
Condominium Building - 38 GPM

ESTIMATED QUANTITY OF SANITARY SEWAGE:

Mansion Building – 110 GPM*
Condominium Building - 126 GPM*

* Source – International Plumbing Code, Tables 709.1, E101B, and E102.

ESTIMATED QUANTITY OF STORM WATER RUNOFF**

** Per DC Department of Health - Watershed Protection Division – quantity of storm water runoff not required to be accounted owing to split drainage system

ZONING COMMISSION
District of Columbia
CASE NO.03-24
EXHIBIT NO.5E