

Exhibit F

SK&I
Architectural Design Group

7735 Old Georgetown Rd. Ste. 1000
Bethesda, MD 20814
Telephone: 301.654.9300
Facsimile: 301.654.7211
Company: @skarch.com

CIVIL ENGINEERS
Edwards & Kelley
Tel: 703.391.7600
Fax: 703.264.0595
E-mail: mlopez@edk.com

LANDSCAPE ARCHITECTS
Parker Rodriguez
Tel: 703.546.8010
Fax: 703.546.8080
E-mail: cmcc@parkerrodriguez.com

INTERIOR DESIGNER
Studios Architecture
Tel: 202.736.5900
Fax: 202.736.9999
E-mail: keffer@studiosarch.com

STRUCTURAL ENGINEERS
Tadon-Cohen-Edison, Inc.
Tel: 301.587.1300
Fax: 301.588.1966
E-mail: ynodman@tadco.com

ME ENGINEERS
GHT Limited
Tel: 703.243.1200
Fax: 703.276.1376
E-mail: rimpson@ghtltd.com

ELECTRICAL DESIGN/BUILD
Cherry Lane Electrical Services
Tel: 301.575.2433
Fax: 301.575.2432
E-mail: bob@clsegroup.com


View 14
Apartments

Washington, DC

PROJECT NO: LVL01
OWNER
L2CP, LLC
1612 U Street, N.W., Suite 401
Washington, DC 20009
Tel: 202.783.1110
Fax: 202.521.0376

REVISION		
50% DD SET		05/31/06
100% DD SET		06/30/06
PROGRESS SET		02/18/06
75% CD SET		02/12/07
RID SET		03/30/07
PERMIT SET		04/15/07
ADDENDUM #2		MAY 26, 2007
ADDENDUM #3		JUN 15, 2007
REVISION / CONSTRUCTION SET		10/01/07
Revision #11		MAY 23, 2008
Revision #13		JULY 03, 2008

KEY PLAN




©2008 SK&I Architectural Design Group, LLC.
THIS PROJECT IS PROTECTED BY COPYRIGHT LAW AND INTERNATIONAL TREATIES

2ND FLOOR
PLAN

DATE 10.01.2007

SCALE 1/8"=1'-0"

A2.06



1 2ND FLOOR PLAN
SCALE: 1/8"=1'-0"

- NOTES
- 1 ALL INTERIOR DIMENSIONS ARE TO FACE OF STUDS UNLESS NOTED OTHERWISE.
 - 2 ALL EXTERIOR DIMENSIONS ARE TO FACE OF BRICK/STONE/BLOCK VENEER OR PROJECTED FACE OF BRICK/STONE/BLOCK VENEER, UNLESS NOTED OTHERWISE.
 - 3 ALL SHAFTHALL DIMENSIONS ARE TO FACE OF G.W.B.
 - 4 ALL UNIT SEPARATION WALLS ARE WALL TYPE SS-66 UNLESS NOTED OTHERWISE.
 - 5 ALL CORRIDOR WALLS ARE WALL TYPE SS-53 UNLESS NOTED OTHERWISE.
 - 6 SEE A3 DRAWINGS SERIES FOR 1/4" SCALE UNIT PLANS FOUR UNIT DIMENSIONS, WALL TYPES, DOOR & WINDOW TYPES, NOTES, ETC.
 - 7 T.O.S. = TOP OF SLAB, T.O.C. = TOP OF CURB, T.O.P. = TOP OF PARAPET OR TOP OF PAVEMENT, F.O.B. = FACE OF BRICK, F.O.M.P. = FACE OF METAL PANEL, F.O.WF. = FACE OF WINDOW FRAME, F.O.M. = FACE OF MANSIONARY.
 - 8 ALL SPOT ELEVATIONS SHOWN ARE T.O.S. UNLESS NOTED OTHERWISE.
 - 9 UNIT DESCRIPTIONS (e.g., 201/ B-06) - THE FIRST NUMBER DENOTES APARTMENT NUMBER AS IT LOCATES ON THE FLOOR, THE SECOND NUMBER DENOTES UNIT TYPE AS IT IS LISTED IN THE UNIT ANALYSIS ON A0.02.
 - 10 PROVIDE 20'X20' 2-HR RETAIL ACCESS DOOR ON FLOOR 2, 4, 6 AND 8 FOR THE MAINTENANCE OF RETAIL KITCHEN EXHAUSTS.