

November, 2014

GASENO.08-07A PARKER

Washington, D.C.







18. WEST ELEVATION (ALLEY)

GRIMM AND PARKER

Washington, D.C.





19. PERSPECTIVE VIEWS - FROM MLK AVENUE








20. PERSPECTIVE VIEWS - MAIN ENTRANCE







2255 MLK JR. AVE, SE 21. PERSPECTIVE VIEWS - LIVE/WORK UNIT ENTRY

2014 GRIMM AND PARKER





22. PERSPECTIVE VIEWS - ROOF TERRACE




























FIBER CEMENT PANELS

PANEL (SMOOTH) W/ REGLETS AND METAL GRAY
FURRING STRIPS. CUSTOM COLORS.



ALUMINUM PANEL:



FACE BRICK: RED BROWN BRICK







26. FACADE DETAILS




Washington, D.C.












SCALE: 3/32" = 1'-0"

GRIMM AND PARKER



2255 MLK JR. AVE, SE







29. SECTION THROUGH RAMP

GRIMM AND PARKER

Washington, D.C.







30. GREEN COMMUNITIES CHECKLIST PAGE 1 & 2







[2 points] or full stormwater retention [6 points]

SUBTOTAL OPTIONAL POINTS

M = MANDATORY

= AVAILABLE OPTIONAL POINTS

4: WATER CONSERVATION YES ONO MAYBE 4.1 Water-Conserving Fixtures Install or retrofit water-conserving fixtures in all units and any common facilities with the following specifications; Toilets—1.28 gpf; Urinals—0.5 gpf; Showerheads—2.0 gpm; Kitchen faucets— 2.0 gpm; Bathroom faucets—1.5 gpm YES ONO MAYBE 4.2 Advanced Water-Conserving Appliances and Fixtures Install or retrofit water-conserving fixtures in all units and any common facilities with the following specifications: Toilets—1.2 gpf; Showerheads—1.5 gpm; Kitchen faucets—1.5 gpm; Bathroom faucets—0.5 gpm. Select any, or all, of the options: • Toilets [2 points] • Showerheads [2 points] • Faucets—kitchen and bathroom [2 points] YES NO MAYBE 4.3 Water Reuse Harvest, treat, and reuse rainwater and/or greywater to meet a portion of the project's water needs. • 10% reuse [1 point] • 30% reuse [3 points] • 20% reuse [2 points] • 40% reuse [4 points] **4 POINTS** SUBTOTAL OPTIONAL POINTS

		5: ENERGY EFFICIENCY
YES NO MAYBE	M	5.1a Building Performance Standard: Single family and Multifamily (three stories or fewer)
	N/A	(New Construction only)
	IN/A	Certify the project under ENERGY STAR New Homes.
YES NO MAYBE	Μ	5.1b Building Performance Standard: Multifamily (four stories or more)
		(New Construction only)
		Demonstrate compliance with EPA's Multifamily High-Rise program (MFHR) using either the prescriptive or the performance pathway.
YES NO MAYBE	M	5.1c Building Performance Standard: Single family and Multifamily (three stories or fewer)
		(Substantial and Moderate Rehab only)
	N/A	Demonstrate that the final energy performance of the building is equivalent to a Home Energy
		Rating System (HERS) Index of 85.
YES NO MAYBE	Μ	5.1d Building Performance Standard: Multifamily (four stories or more)
	N/A	(Substantial and Moderate Rehab only)
		Demonstrate that the final energy performance of the building is equivalent to ASHRAE 90.1-2007.
YES NO MAYBE	15	5.2 Additional Reductions in Energy Use
	max	Improve whole-building energy performance by percentage increment above baseline building
		performance standard for additional points.
YES NO MAYBE	Μ	5.3 Sizing of Heating and Cooling Equipment
		Size heating and cooling equipment in accordance with the Air Conditioning Contractors of America
		(ACCA) Manuals, Parts J and S, or ASHRAE handbooks.
YES ONO MAYBE	M	5.4 ENERGY STAR Appliances



2 POINTS

2255 MLK JR. AVE, SE

31. GREEN COMMUNITIES CHECKLIST PAGE 3 & 4



If providing appliances, install ENERGY STAR-labeled clothes washers, dishwashers, and refrigerators.

M = MANDATORY# = AVAILABLE OPTIONAL POINTS **ENERGY EFFICIENCY (CONTINUED)** YES ONO OMAYBE 5.5a Efficient Lighting: Interior Units Follow the guidance appropriate for the project type: install the ENERGY STAR Advanced Lighting Package (ALP); OR follow the ENERGY STAR MFHR program guidelines, which require that 80% of installed lighting fixtures within units must be ENERGY STAR-qualified or have ENERGY STARqualified lamps installed; OR if replacing, new fixtures and ceiling fans must meet or exceed ENERGY STAR efficiency levels. YES ONO MAYBE 5.5b Efficient Lighting: Common Areas and Emergency Lighting Follow the guidance appropriate for the project type: use ENERGY STAR-labeled fixtures or any equivalent high-performance lighting fixtures and bulbs in all common areas: OR if replacing. new common space and emergency lighting fixtures must meet or exceed ENERGY STAR efficiency levels. For emergency lighting, if installing new or replacing, all exit signs shall meet or exceed LED efficiency levels and conform to local building codes. YES ONO MAYBE 5.5c Efficient Lighting: Exterior Follow the guidance appropriate for the project type: install ENERGY STAR-qualified fixtures or LEDs with a minimum efficacy of 45 lumens/watt; OR follow the ENERGY STAR MFHR program guidelines, which require that 80% of outdoor lighting fixtures must be ENERGY STAR-qualified or have ENERGY STAR-qualified lamps installed; OR if replacing, install ENERGY STAR compact fluorescents or LEDs with a minimum efficacy of 45 lumens/watt. YES NO MAYBE **5.6a Electricity Meter** (New Construction and Substantial Rehab only) Install individual or sub-metered electric meters in all dwelling units. O YES O NO O MAYBE **5.6b Electricity Meter** (Moderate Rehab only) Install individual or sub-metered electric meters in all dwelling units. N/A 12 Install photovoltaic (PV) panels, wind turbines, or other electric-generating renewable energy source to provide a specified percentage of the project's estimated energy demand. 5.7b Photovoltaic/Solar Hot Water Ready Site, design, engineer, and/or plumb the development to accommodate installation of photovoltaic (PV) or solar hot water system in the future. YES NO MAYBE 5.8 Advanced Metering Infrastructure Site, design, engineer, and wire the development to accommodate installation of smart meters and/or be able to interface with smart grid systems in the future. **5 POINTS** SUBTOTAL OPTIONAL POINTS **6: MATERIALS BENEFICIAL TO THE ENVIRONMENT** YES ONO MAYBE 6.1 Low/No VOC Paints and Primers All interior paints and primers must be less than or equal to the following VOC levels: Flats —50 g/L; Non-flats-50 g/L; Floor-100 g/L YES ONO MAYBE 6.2 Low/No VOC Adhesives and Sealants All adhesives must comply with Rule 1168 of the South Coast Air Quality Management District. All caulks and sealants must comply with regulation 8, rule 51, of the Bay Area Air Quality Management District. YES ONO MAYBE 6.3 Construction Waste Management Commit to following a waste management plan that reduces non-hazardous construction and

= AVAILABLE OPTIONAL POINTS MATERIALS BENEFICIAL TO THE ENVIRONMENT (CONTINUED) YES ONO MAYBE 6.4 Construction Waste Management: Optional Determine percentage of waste diversion and earn all points below that threshold: 35% waste diversion [1 point] • 65% waste diversion [1 point] 1 • 45% waste diversion [1 point] • 75% waste diversion [1 point] • 55% waste diversion [1 point] YES NO MAYBE 6.5 Recycling Storage for Multifamily Project Provide one or more easily accessible, permanent areas for the collection and storage of materials 5 YES ONO MAYBE 5 6.6 Recycled Content Material Incorporate building materials that are composed of at least 25% post-consumer recycled content or at least 50% post-industrial recycled content. Select from the following: • Framing materials [1 point] • Exterior materials: siding, masonry, roofing [1 point] Concrete / cement and aggregate [1 point] Drywall/interior sheathing [1 point] Flooring materials [1 point] YES NO MAYBE 6.7 Regional Material Selection Use products that were extracted, processed, and manufactured within 500 miles of the home or max building for a minimum of 50% of the building material value (based on cost). Select any or all of these options: • Framing materials [1 point] Exterior materials: siding, masonry, roofing [1 point] Concrete / cement and aggregate [1 point] Drywall/interior sheathing [1 point] • Flooring materials [1 point] O YES NO O MAYBE 6.8 Certified, Salvaged, and Engineered Wood Products Commit to using wood products and materials of at least 25% that are (by cost): FSC-certified, salvaged products, or engineered framing materials without urea-formaldehyde binders. 6.9a Reduced Heat-Island Effect: Roofing Use Energy Star-compliant roofing or install a "green" (vegetated) roof for at least 50% of the roof area. Select only one: cool roof [3 points] or green roof [1 point] O YES NO O MAYBE 6.9b Reduced Heat-Island Effect: Paving Use light-colored, high-albedo materials and/or an open-grid pavement, with a minimum solar reflectance of 0.3, over at least 50% of the site's hardscaped area 13 POINTS SUBTOTAL OPTIONAL POINTS 7: HEALTHY LIVING ENVIRONMENT YES NO MAYBE 7.1 Composite Wood Products that Emit Low/No Formaldehyde All composite wood products must be certified compliant with California 93120. If using a composite wood product that does not comply with California 93120, all exposed edges and sides must be sealed

M = MANDATORY

FOUR = POINTS

2255 MLK JR. AVE, SE

32. GREEN COMMUNITIES CHECKLIST PAGE 5 & 6

with low-VOC sealants.



Washington, D.C.

demolition waste by at least 25% by weight through recycling, salvaging, or diversion strategies.

HEALTHY LIVING ENVIRONMENT (CONTINUED) YES ONO MAYBE 7.2 Environmentally Preferable Flooring Do not install carpets in entryways, laundry rooms, bathrooms, kitchens/kitchenettes, utility rooms, and all rooms of ground-connected floors. Any carpet products used must meet the Carpet and Rug Institute's Green Label or Green Label Plus certification for carpet, pad, and carpet adhesives. Any hard surface flooring products used must be either ceramic tile, unfinished hardwood floors, *OR* in compliance with the Scientific Certification System's FloorScore program criteria. NO () MAYBE 7.3 Environmentally Preferable Flooring: Alternative Sources Use non-vinyl, non-carpet floor coverings in all rooms of building. YES NO MAYBE **7.4a Exhaust Fans: Bathroom** (*New Construction and Substantial Rehab only*) Install Energy Star-labeled bathroom fans that exhaust to the outdoors, are connected to a light switch, and are equipped with a humidistat sensor, timer, or other control (e.g., occupancy sensor, delay off switch, ventilation controller). O YES O NO O MAYBE **7.4b Exhaust Fans: Bathroom** (Moderate Rehab only) Install Energy Star-labeled bathroom fans that exhaust to the outdoors, are connected to a light switch, N/A and are equipped with a humidistat sensor, timer, or other control (e.g., occupancy sensor, delay off switch, ventilation controller). res O NO O MAYBE **7.5a** Exhaust Fans: Kitchen (New Construction and Substantial Rehab only) Install power-vented fans or range hoods that exhaust to the exterior at the appropriate cfm rate, per ASHRAE 62.2, or install a central ventilation system with rooftop fans that meet efficiency criteria. YES NO MAYBE **7.5b Exhaust Fans: Kitchen** (Moderate Rehab only) Install power-vented fans or range hoods that exhaust to the exterior at the appropriate cfm rate, per ASHRAE 62.2, or install a central ventilation system with rooftop fans that meet efficiency criteria. N/A YES ONO MAYBE **7.6a Ventilation** (New Construction and Substantial Rehab only) Install a ventilation system for the dwelling unit capable of providing adequate fresh air per ASHRAE requirements for the building type. O YES O NO O MAYBE **7.6b Ventilation** (*Moderate Rehab only*) Install a ventilation system for the dwelling unit capable of providing adequate fresh air per ASHRAE requirements for the building type. N/A 7.7 Clothes Dryer Exhaust Clothes dryers must be exhausted directly to the outdoors using rigid-type duct work. ES NO MAYBE 7.8 Combustion Equipment Specify power-vented or closed-combustion equipment when installing new space and water-heating equipment in New Construction and any Substantial and Moderate Rehab projects. FS O NO O MAYBE 7.9a Mold Prevention: Water Heaters Provide adequate drainage for water heaters that includes drains or catch pans with drains piped to the exterior of the dwelling. ES NO MAYBE 7.9b Mold Prevention: Surfaces In bathrooms, kitchens, and laundry rooms, use materials that have durable, cleanable surfaces. YES NO MAYBE 7.9c Mold Prevention: Tub and Shower Enclosures Use non-paper-faced backing materials such as cement board, fiber cement board, or equivalent in bathrooms.

M = MANDATORY
= AVAILABLE OPTIONAL POINTS

HEALTHY LIVING ENVIRONMENT (CONTINUED) 7.10 Vapor Barrier Strategies (*New Construction and Rehab Projects with foundation work only*) Install vapor barriers that meet specified criteria appropriate for the foundation type. **7.11 Radon Mitigation** (*New Construction and Substantial Rehab only*) For New Construction in EPA Zone 1 and 2 areas, install passive radon-resistant features below the slab. For Substantial Rehab projects in those Zones, test for the presence of radon and mitigate if elevated levels exist. **7.12 Water Drainage** (New Construction and Rehab projects replacing assemblies called out in Criterion only) Provide drainage of water away from windows, walls, and foundations by implementing list of techniques. YES NO MAYBE M 7.13 Garage Isolation Follow list of criteria for projects with garages, including: provide a continuous air barrier between the conditioned (living) space and any garage space to prevent the migration of any contaminants into N/A the living space, and install a CO alarm inside the house in the room with a door to the garage and outside all sleeping areas. YES NO MAYBE 7.14 Integrated Pest Management Seal all wall, floor, and joint penetrations with low-VOC caulking or other appropriate sealing methods M **7.15 Lead-Safe Work Practices** (Substantial and Moderate Rehab only) For properties built before 1978, use lead-safe work practices consistent with the EPA's Renovation, N/A Repair, and Painting Regulation and applicable HUD requirements. YES ONO MAYBE 7.16 Smoke-Free Building 9 Implement and enforce a no smoking policy in all common, individual living areas, and with a 25-foot perimeter around the exterior of all residential buildings.

		8: OPERATIONS + MAINTENANCE
YES NO MAYBE	Μ	8.1 Building Maintenance Manual (All Multifamily Projects) Provide a building maintenance manual that addresses maintenance schedules and other specific instructions related to the building's green features.
YES NO MAYBE	M	8.2 Resident Manual Provide a guide for homeowners and renters that explains the intent, benefits, use, and maintenance of green building features.
YES NO MAYBE	M	8.3 Resident and Property Manager Orientation Provide a comprehensive walk-through and orientation for residents and property managers using the appropriate building maintenance or resident's manual.
YES NO MAYBE	12	8.4 Project Data Collection and Monitoring System Collect and monitor project performance data on energy, water, and, if possible, healthy living environments for a minimum of five years.

0 POINTS

9 POINTS

SUBTOTAL OPTIONAL POINTS

SUBTOTAL OPTIONAL POINTS

46 POINTS

TOTAL OPTIONAL POINTS



M = MANDATORY

= AVAILABLE OPTIONAL POINTS

2255 MLK JR. AVE, SE

33. GREEN COMMUNITIES CHECKLIST PAGE 7 & 8

