

EROSION AND SEDIMENT CONTROL NOTES

SOME IMPACT TO ADJACENT PROPERTIES IS ANTICIPATED FROM THE PROPOSED CONSTRUCTION. IMPACTS TO THE NORTHERN ADJACENT PROPERTY WILL BE LIMITED TO THE CONSTRUCTION OF THE NORTH BUILDING. SHEETING AND SHORING WILL BE INSTALLED AT THE REQUIRED LOCATIONS AS NEEDED.

ALL UTILITY WORK SHALL BE COMPLETED IN PHASES AND PLATED AS NEEDED TO COVER TRENCHING. ALL TRENCHING WORK SHALL BE STABILIZED AT THE END OF EACH WORKING DAY. CONTRACTOR SHALL WORK CLOSELY WITH THE INSPECTOR TO ENSURE AREAS ARE STABILIZED TO DOEE STANDARD.

STANDARD SYMBOLS

FOR EROSION AND SEDIMENT CONTROL PRACTICES

TITLE	KEY	SYMBOL
STABILIZED CONSTRUCTION ENTRANCE	SCE	
INLET PROTECTION	IP	
SAFETY FENCE	SAF	
SUPER SILT FENCE	SSF	

